

THE
ARCHITECT
& BUILDING NEWS

11 OCTOBER 1956 · VOL. 210 · NO. 15 · ONE SHILLING WEEKLY

• STORE, SOUTHAMPTON

• SOLAR HOUSE, RICKMANSWORTH

• INFORMATION DIGEST

PUBLISHED IN LONDON SINCE 1854

WHERE SIMPLE OR COMPLICATED SCHEMES OF VENTILATION ARE INSTALLED, AND THE OPERATION IS REQUIRED, BY REMOTE CONTROL OR OTHERWISE, AND THE WINDOWS HAVE ANY OF THE FOLLOWING CHARACTERISTICS :—

- OPENING OUTWARDS
- OPENING INWARDS
- TOP HUNG
- HORIZONTAL CENTRE-HUNG
- BOTTOM HUNG
- VERTICAL PIVOT HUNG
- SIDE HUNG
- HORIZONTAL SLIDING
- VERTICAL SLIDING



The illustration shows One Set of Electrically operated Twin Tension Rod Gear with Counter-Balance Unit operating one continuous opening light, 74' 0" long x 5' 0" deep. Note the Spiral Balance Wheel fitted at the end Sprocket.

Always Specify **WINDOW OPENING GEAR** *for*
SKYLIGHTS, LANTERN LIGHTS, CLERESTORY LIGHTS, FANLIGHTS, SIDE WALL
LIGHTS IN WOOD OR METAL WINDOWS, OR IN PATENT GLAZING, ROOF LIGHTS
AND BENCH LIGHTS IN GREENHOUSES, DAMPERS, TRAP DOORS, SHIPS SKYLIGHTS, ETC.
HAND - OPERATED — ELECTRIC — HYDRAULIC — REMOTE CONTROL
by **WILLIAM NEWMAN & SONS LTD.**
HOSPITAL STREET, BIRMINGHAM

GEARING DEPT. BRANCH WORKS 3 WELLHEAD LANE, PERRY BARR, BIRMINGHAM



Architects: H. Wakeford & Sons, L.R.I.B.A.
General Contractors: Messrs. Percy Bilton Ltd.

EXPRESS DAIRIES CHOOSE CERAMIC TILES

In the hands of hygiene rests a nation's health. Cleanliness cannot be left to chance. That is why Express Dairies chose genuine Ceramic Tiles for the walls of their fine modern Bottling Centre, Where there can be no other course than maximum hygiene and cleanliness . . . there can be no other choice than genuine Ceramic Tiles.

Ceramic

T I L E S

Glazed & Floor Tile Manufacturers' Association · Federation House · Stoke-on-Trent

Before

you change

over...

..... May we ask you to contact us for full details of the new series 'Potterton' Oil-Fired Boiler-Burner Units with ratings up to 1,000,000 B.t.u./hr.

These Boiler-Burner Units, like the smaller series, are designed for easy maintenance, automatic operation on 200 Sec Oil and continuous working efficiency in the 80% range. One of the major features of the design is the incorporation of a fan at the flue outlet to ensure positive egress of products of combustion in any existing chimney or flue, and operating temperatures do not exceed 350° F.



All 'Potterton' industrial oil-fired boilers are clad in 'Formica'.

Cost of Living. Provided no major factors intervene, the price of De La Rue products will be stabilised until March 31st 1957.

'Potterton' Oil-Fired Boiler-Burner Units

give you the most heat from every drop of oil.



THOMAS DE LA RUE & CO. LTD., (Potterton Division) Cavendish Works, 20/30 Buckhold Road, London S.W.18.



**GOOD LOOKS
AREN'T ALL —**

VELSET

emulsion paint

**—has these EXTRA
advantages**

Velset is an ideal interior decoration—Can be used on NEW Plaster—concrete—brick, paper etc. Quick drying, a second coat can normally be applied within 2 hours.

Easily applied—by brush, spray or roller—almost odourless—ideal for factories, canteens, hospitals. Economical—Velset has great covering capacity.

**RAINES &
PORTER LTD.**

TRANBY WORKS WINGOLMLEE HULL

Telephone 34683

LONDON

BOWLES ROAD, S.E.1
Tel. BERMONDSEY 2575

NEWCASTLE-ON-TYNE


28 LEAZES PARK ROAD
Tel. 27890

GLASGOW


CUMBERLAND LANE, C.5
Tel. SOUTH 1896



Woodberry Down School . . .



is fitted with L.E.F. Raising & Lowering Gear



THE means of servicing inaccessible lights in the Assembly Hall of this new school was given careful consideration at an early stage of planning by the Architect (Robert H. Matthew, C.B.E., A.R.I.B.A.) and the Chief Engineer L.C.C. (J. Rawlinson, C.B.E., M.Eng., M.I.C.E., M.I.Mech.E.)

London Electric Firm Ltd., were consulted, with the result that they were able to supply Raising and Lowering Gear that was built into the ceiling with all working parts concealed.

L.E.F. Raising and Lowering Gear enables maintenance staff to bring light fittings down to floor level so that they can be dealt with quickly and conveniently. It outdates other cumbersome methods and is more economical in time and labour.

When you have a similar lighting problem, remember that it is most important to discuss your needs with L.E.F. at the planning stage ; first to satisfy your technical requirements and secondly to ensure suitable delivery.

LONDON ELECTRIC FIRM LTD. South Croydon, Surrey. Telephone: Uplands 4871





"You'll find that years of rough treatment won't damage Stelcon Floors."

Where factory traffic is toughest, put down Stelcon Floors. They pay for themselves by saving costly repairs. Being level and *staying* level, they keep things smooth-running, not only inside but outside on loading bays, runways, etc. In fact, Stelcon Floors are ideal—dustless, hygienic and perfectly suited to modern mechanical handling methods.





You'll find
Stelcon
FLOORS
in every industry
—everywhere



Stelcon Anchor Steel Plates are what their name implies—steel anchored and bedded down in concrete. In fact, it would take a bomb to break up a Stelcon Floor!

NEW WORLD TO THE RESCUE

The need under Operation Rescue for a complete hot water service where none already exists has turned the attention of Architects and Municipal Authorities to the **NEW WORLD** Gas Storage Systems.




NEW WORLD Storage Water Heaters are reasonably priced, easily fitted, economical to use, provide hot water at the same temperature, Summer and Winter, can normally be operated on the existing Gas and Water Services and require an absolute minimum of maintenance.

As an example, the **NEW WORLD** C.12.S. Circulator, fitted to a lagged 20-gallon cylinder, can be accommodated under the draining board in the kitchen. With the Economy Valve, the user has the choice of heating 4 gallons for the sink and wash-basin or 20 gallons when a bath is required. The temperature of the water is automatically controlled by the Regulo. If ventilation in the kitchen is adequate no flue is needed. This installation is being extensively used in new houses and flats, and for the modernising and conversion of old property.

A similar type of installation is available for use in an airing cupboard; and when the house contains no ball valve cistern, a combination unit complete with cistern mounted on the cylinder can be supplied.

recommend




storage water heaters

Further information from

RADIATION GROUP SALES LTD., 7 STRATFORD PLACE, LONDON, W.1. Phone: MAYfair 6462

U
P
W
A
R
D
S
!



Rolador Shutter 12 ft. wide x 35 ft. high.

Haskins

make shutters which
will protect any opening,
any height, any width.


For steel doors that
COIL, FOLD or SLIDE.

Consult Haskins.

The two examples illustrated
are the ROLADOR steel
rolling shutter and the steel
folding SHUTTER DOOR.

ROLADOR
STEEL ROLLING SHUTTERS
& FOLDING SHUTTER DOORS

S I D E W A Y S !



2 Shutter doors each 30 ft. wide x 18 ft. high.

Full
information
including
working
clearances
and fixing
details
supplied
upon
request.


Haskins,
Gnome House,
Blackhorse Lane,
London, E.17.
Tel :
LARKSWOOD 2622
and Brook Street,
Basingstoke,
Hants.
Tel :
Basingstoke 1070

LANDMARKS IN STEEL




STEELWORK for MODERN LIVING

Dominating not only by reason of its size, but by its bold conception, this great block of flats and shops on the front at St. Leonards-on-Sea is a fine example of modern construction, with Steelwork by—



Architects:
Dalglish & Pullen F/A.R.I.B.A.,
17 Fitzhardings Street,
London, W.1.
Civil Engineers:
S. H. & D. E. White,
9 Victoria Street, London, S.W.1.
General Contractors:
Griggs & Son Ltd.,
56 Victoria Street, Westminster,
London, S.W.1



Registered Office & Works: MANCHESTER 17
Telephone: TRAFFORD PARK 2341 (10 lines)

London Office: 68 Victoria Street, S.W.1. Telephone: VICTORIA 1331/2. Technical Offices: Birmingham and Loughborough.



Background to Beauty. Pearl grey 'VITROLITE' by Pilkington Brothers Limited, St. Helens, Lancs.

'VITROLITE' IS AVAILABLE IN THE FOLLOWING COLOURS: PEARL GREY, PRIMROSE, GREEN, GREEN AGATE, TURQUOISE, EGG SHELL, CREAM, IVORY, BLACK, WHITE.
SUPPLIES ARE AVAILABLE THROUGH THE USUAL TRADE CHANNELS. 'Vitrolite' is a registered trade mark of Pilkington Brothers Limited.

YOU CAN NOW BUY


CANADIAN DOUGLAS FIR PLYWOOD

— every panel bonded with Phenolic Formaldehyde Glue!

You are invited to
visit the
CANADIAN GOVERNMENT
TIMBER EXHIBIT
STANDS 74-75
MANCHESTER BUILDING
TRADES EXHIBITION
October 16—27



for Flooring



for Shuttering



for Roof Sheathing

FOR FURTHER INFORMATION concerning
Canadian woods contact The Commercial
Counsellor (Timber), Canada House,
Trafalgar Sq., London, S.W.1

Canadian Douglas Fir Plywood is:

Easy to handle Speedy to use

Split-proof Dimensionally stable

Bonded with Phenolic Formaldehyde Glue

This advertisement is one of a series featuring Canadian Spruce, White Pine, Western Red Cedar, Red Pine and Pacific Coast Hemlock.

To Architects about to plan Roofs....

BRIGGS ADVISORY SERVICE

Every Architect in the country should know about Briggs Advisory Service—we believe it is the most comprehensive in the Roofing Industry.

It offers:—

- 1** The services of a highly organised Drawing Office ready to prepare, in collaboration with yourselves, complete working drawings.
- 2** The assistance of experienced Roofing Technicians to advise on every detail of modern roof construction.
- 3** The results of constant research in roof design and construction, and the accumulated knowledge of a large nation-wide roofing organisation

Our nearest Area Office can give you further details of this Service, which is, of course, entirely free and without obligation.



BITUMETAL

**ROOF plus
CEILING plus
INSULATION**

WILLIAM BRIGGS & SONS LIMITED
LONDON: Vauxhall Grove, S.W.8. Regd. Office: GUNDEE

Area Offices and fully equipped installations also at: ABERDEEN, BELFAST, BRISTOL, DUBLIN, EDINBURGH, GLASGOW

Barry's Heavy Ruboleum

MONARCH OF THE LINOLEUM WORLD SINCE 1907



Reproduction of a RUBOLEUM Floor in a Food Store

HEAVY RUBOLEUM is a superfine linoleum 6.70 mm. thick (approx. $\frac{1}{4}$ "), was first produced by us in 1907, and still holds its position of the highest merit as a floorcovering because of its properties of hygiene, resilience, durability and decorative colourings.

HEAVY RUBOLEUM is produced in 35 beautiful and popular colours, plain and marble effects.

HEAVY RUBOLEUM is especially produced for use on Ship decks and Public buildings. It is available through high-class retail Furnishers and Contract Flooring Specialists.

HEAVY RUBOLEUM is the solution to your flooring problems.

SAMPLES ON APPLICATION TO THE EXCLUSIVE MANUFACTURERS

**BARRY, OSTLERE
KIRKCALDY**



**SHEPHERD, LTD
SCOTLAND**



*Architects: Sir John Burnet, Tait and Partners. Quantity Surveyors: Messrs. E. C. Harris & Partners.
Consulting Engineer: Alfred E. Beer, Esq., A.C.G.I., A.M. I.C.E., M.I. Struct. E.*

Monsanto House, Victoria Street, Westminster, for Site Improvements Ltd.

This important contract was carried out by Cubitts' Structural Engineering and Building Departments. Precast concrete construction has been used for the main frame, external panel walling and staircases. An average of 10 days for the erection of each floor of nearly 13,000 square feet was maintained.

ENGLAND · SCOTLAND · OVERSEAS

With the experience of the past
CUBITTS
build for the future

HOLLAND & HANNEN AND CUBITTS LIMITED · ONE QUEEN ANNE'S GATE · WESTMINSTER · S.W.1

TGA C126C



Worth looking into...

The interior of a typical absorption tower under construction, showing grillage.

Ancorite

ANCORITE LIMITED

THE CHEMICAL ENGINEERING DIVISION OF THE GENERAL ASPHALTE COMPANY LIMITED

GRAFTON ROAD, LONDON, N.W.5. TEL: GUL 7171 (7 LINES)

T.A. 8966

Ancorite Ltd., Plant Division, are specialists in the design and construction of absorption towers and in the lining of circulation, process and storage tanks, reaction vessels, crystallizers and other equipment.

Our Industrial Flooring Division has a wide experience in the laying of heavy duty process floors, channels and chemical drainage systems.

Ancorite Anti-corrosive Cements are used throughout by our skilled operatives.

A "Star" attraction

Sundeala

METAL FIXING SYSTEMS

*offer Thermal Insulation and Sound Insulation
plus a perfect ceiling*



Britvic Products Ltd., Chelmsford. Staff Restaurant.

Architects: Messrs. Llewellyn Smith & Waters, for C.A.S. (INDUSTRIAL DEVELOPMENTS) Ltd.
Builders: C.A.S. (Contractors) Ltd.

Specify Sundeala Concealed Fixings
for jobs needing refinement in finish
V. Clip fixings for factories etc.

Full particulars and Technical Service from


SUNDEALA BOARD CO. LIMITED

Head Office: ALDWYCH HOUSE, LONDON, W.C.2. Tel: CHAncery 8159

or from its Office at

Newcastle: NORTHUMBRIA HOUSE, PORTLAND TERRACE, 2

LEAD INSPIRES




The new
Flèche for
the Guildhall

Architects: Sir Giles Scott, Son & Partner
General Contractors: Trollope & Colls Ltd.

h

LEAD LASTS

The Council's Technical Information Bureau will gladly help with problems on the use of Lead Sheet and Pipe in building work. Publications that give details of the main uses are freely available. Please state the particular interest when applying for copies.



The new
Dutch Church
Austin Friars

Architect: Arthur Bailey, O.B.E., F.R.I.B.A.
General Contractors: Trollope & Colls Ltd.

LEAD SHEET AND PIPE COUNCIL in association with LEAD DEVELOPMENT ASSOCIATION

EAGLE HOUSE • JERMYN STREET • LONDON S.W. 1

Telegrams: Ukleadman, Piccy, London

Telephone: Whitehall 4175

B136

ELLARD

ESTATE

SLIDING DOOR GEAR



The illustration on right shows yet another example of the use of ELLARD "Estate" Sliding Door Gear in the modern dwelling house. See how simple it is to convert a spacious room to one of a cosy and intimate atmosphere. The fingertip smoothness of door action offers immediate reduction of living space when desired with the additional

advantage of fuel economy. Elegant appearance, ease of operation and long service are the main selling features of this attractive ELLARD Door Gear. Excellent design, moderate cost and maximum use of floor space make ELLARD Door Gear the obvious choice for both council estates and private houses.



RADIAL

SLIDING DOOR GEAR

Illustration on left shows ELLARD "RADIAL" Sliding Door Gear fitted to a private garage. Sliding doors are of great advantage in protecting cars against damage caused by accidental swinging of hinged doors. In addition, valuable working space is offered where it is most desired at the entrance to the garage. Note also how ELLARD Door Gear provides easy access to and from the garage by a personal entry door. ELLARD "Radial" Sliding Door Gear is low in price and gives long service without maintenance. This gear is also suitable for the larger openings of commercial and industrial garages

OVERDOR

GARAGE DOOR GEAR

ELLARD "Overdor" gear, illustrated on right, represents the best method of operating an overhead-type door, and it requires the minimum space, fixing time and maintenance. An entirely clear threshold is achieved, and both side walls are available for windows or shelves. "Overdor" gear is designed for doors from 6ft. to 7ft. 3ins. high and up to 200lbs. in weight. The door is safely balanced and can be opened and closed with ease. The width of the door is not critical but the construction should ensure that the door does not sag when in the raised horizontal position, and we suggest a maximum width of 10ft. The balance springs impose a maximum force along the jambs, thus relieving the building of all stress until the door is raised, when less than half the weight of the door is supported by the twin top tracks. ELLARD "Overdor" is therefore especially suitable for lightly constructed buildings.




Immediate delivery of ELLARD "Estate", "Radial" and "Overdor" Sliding Door Gear can be obtained from large ironmongers and builders' merchants throughout the country.

ELLARD SLIDING DOOR GEARS LTD., WORKS ROAD, LETCHWORTH, HERTS.

TEL: 613/4

BMJ



TWO POINTS TO REMEMBER WHEN PLANNING FOR KITCHENS



THE FLAVEL GAS-HEATED 'SUNTRAP' CLOTHES DRYER

(for single dwelling installations)

THIS CLOTHES DRYER is strongly constructed of zinc-coated steel sheet, finished in cream enamel paint. Fitted with double doors, and heated by means of a gas-burner unit in the base, the Dryer is large enough to contain an average weekly wash. The clothes are hung on eleven tubular bakelite rails at three



different heights. A guard is provided above the burner unit and the gas-rate is controlled by means of a constant-pressure governor. Gas rate 10,000 B.Th.U. per hr. (20 cu. ft./hr. of 500 C.V. gas). Connection $\frac{1}{4}$ inch B.S.P.

The Flavel 'Suntrap' Clothes Dryer is constructed so that it can be supplied either as a complete unit or, alternatively, for building into a recess or corner by utilising the main frame assembly and such component parts as may be necessary.



For fuller details, you are invited to write to Flavels. Their Architectural Advisory Bureau is always ready to give expert advice and information about all Flavel Appliances ... solid fuel grates, boilers, cooker/water heaters, gas-heated clothes dryers, water heaters, fires and cookers.

THE FLAVEL 'NATIONAL' INSTANTANEOUS SINK GAS WATER HEATER

Provides a full half-gallon of piping hot water every minute, at a farthing a gallon. A broken feed type heater, with all working parts totally enclosed. Designed for wall fixing, it works equally well on both hard and soft water.

★ ★ ★

Slim, easily detachable one-piece steel case finished in sparkling, clean-at-a-wipe cream or white vitreous enamel.

★ ★ ★

The removal of a single knurled nut enables the heat exchanger to be unhooked and cleaned in less than five minutes.

★ ★ ★

12 non-clogging Bray burner jets. Rating: 35,000 B.Th.U./hr. Connections: Gas $\frac{1}{4}$ " B.S.P.; water $\frac{1}{2}$ " B.S.P.



Height 25 $\frac{1}{2}$ ", width 8 $\frac{1}{2}$ ", depth 7 $\frac{1}{4}$ ", weight 20 $\frac{1}{2}$ lbs. 6" spout supplied as standard, but 9" 12" or 18" spouts are available.

SEE A FLAVEL FIRST

SIDNEY FLAVEL & CO. LTD., LEAMINGTON SPA. TELEPHONES: (SALES) 3091 AND 8700. TELEGRAMS: FLAVELS

Single or Double?



HILLSULATE

REGD. TRADE MARK

DOUBLE GLASS CLEAR PANELS

Light without heat loss—comfort with economy—“HILLSULATE” Double Glass Clear Panels are better from every point of view. Their high thermal value (equivalent to 4½ in brickwork) enables the modern demand for larger glazing areas to be met without any increased heat loss. As a consequence, less fuel is required and a smaller heating plant, at lower capital cost, may be sufficient. Comfortable inside temperatures can be easily maintained throughout the changing seasons, and condensation is virtually eliminated.

The Panels consist of two panes of clear sheet glass ⅜ in apart, continuously sealed along all edges to provide an air-tight cavity and fitted with an aluminium surround. They are made to measure up to 48 in wide with an area not exceeding 25 sq. ft.

MANUFACTURED AND SUPPLIED BY

(WEST BROMWICH)


HILLS LIMITED

- ✓ Metal surround protects airtight cavity seal
- ✓ Increases daylight without heat loss
- ✓ Handled as easily as a single pane of glass
- ✓ Can be glazed into any normal window rebate
- ✓ Reduces heating costs
- ✓ Virtually eliminates condensation



Architects are invited to write for illustrated literature and price list.

ALBION ROAD, WEST BROMWICH, Staffs. Tel.: West Bromwich 1811 (15 lines). LONDON: CHAPONE PLACE, DEAN STREET, W.1 Tel.: GERard 0526/9. Branches at Birmingham (Midland 5175), Manchester (Blackfriars 3382), Bristol (24765), Newcastle-on-Tyne (25060), Glasgow (City 5564) and Belfast (26112).



'Pyrotenax' are pleased to announce that all their standard 600 volt and lighting cables can now be supplied "off the shelf," from their Hebburn Works and from 78 officially appointed Wholesaler/Stockist establishments conveniently situated throughout Great Britain.

The use of the trade name 'Pyrotenax' is exclusive to the products of this Company and its associates.

PYROTENAX LIMITED • HEBBURN-ON-TYNE

Phone: HEBBURN 32244/7


LONDON
Phone: Abbey 1654/5
GD 31

BIRMINGHAM
Phone: Midland 1265

MANCHESTER
Phone: Blackfriars 6946

LEEDS
Phone: Leeds 27826

GLASGOW
Phone: Central 2238



CLEAR CAVITY PLYGLASS throughout giving essential insulation
COLOURED VITROSLAB as an architectural design element
SLATTED PLYGLASS internally for functional decor

PLYGLASS LTD Works: SANDHURST CLOSE, SOUTH CROYDON, SURREY
EDINBURGH WAY, HARLOW, ESSEX

Manufacturers of VITROSLAB infilling panels for CURTAIN WALLING. HEAT INSULATING LIGHT
DIFFUSING PLYGLASS for the glazing of translucent roofs and walls. Clear Cavity Plyglass for insulation.
Also FIBROPANE & CONTRALUX GLASS for suspended ceilings.

Better heating...

designed for the modern store



Illustrated is a self-service store equipped with G.E.C. 3kW heaters

G.E.C.

ELECTRIC UNIT HEATERS


For further information, please write for Publication H.O. 2634
THE GENERAL ELECTRIC CO. LTD., MAGNET HOUSE, KINGSWAY, LONDON W.C.2



Warm in winter Embodying self-contained heat sources and circulating fans, G.E.C. 3kW heaters maintain a constant temperature in every part of the store. Circulating continuously, the air is rapidly warmed. Refrigerated displays are unaffected and there is no food-contaminating dirt.


Cool in summer The circulating fan can be used independently to create a current of cool air all over the store.

Smart and efficient all-year-round The louvred body is ideally shaped for the circulation of warm or cool air and the modern appearance of the heater blends harmoniously with the decor of an up-to-date store.



A BIG saving on installation costs

Rolyat tanks represent a saving all along the line, quite apart from the extra quality which is built into them. Special tanks are made for awkward situations at no extra cost, and an advisory service is at your command for any installation. They are specified by local authorities, Architects and Heating Engineers throughout the country.



Illustrated is the 25 gallon "Rolyat" recessed "Durham" tank. Please send me details of the range of "Rolyat" tanks.

NAME _____
ADDRESS _____
A/I


ROLYAT TANKS

PATENT HOT WATER

THE ROLYAT TANK CO. LTD. CROMWELL RD. YORK

In the 'Solar' Experimental House

(Rickmansworth)



... you will find **'Paramount' Dry Partition**

Mr. E. J. W. Curtis, A.R.I.B.A., the architect, specified 'Paramount' Dry Partition because it's easy to handle, quickly erected, light in weight, it is good for thermal and sound insulation and is fire-resisting. It is, in fact, almost a ready-made wall. 'Paramount' Dry Partition has a wide range of applications and even off-cuts, having the same strength as the original panel, can be used in the construction of cupboards, etc. Fixing recommendations and complete details are given in the booklet "Paramount Dry Partition" sent free on request. 'Paramount' Dry Partition is obtainable from Builders' Merchants everywhere.

'Paramount' Dry Partition

THE BRITISH PLASTER BOARD (MANUFACTURING) LIMITED

BATH HOUSE · 82 PICCADILLY · LONDON, W.1.

Telephone: Grosvenor 8311

FLYASIDE GEAR—*the best for doors like these*

**SILENT BALL BEARING ACTION
NO STICKING—NON CORROSIVE**

Flyaside Gear, first made by us twenty years ago, is designed to take domestic doors up to 100 lbs. weight. Other models for heavier doors are available.

The registered design of track is the most effective of any, keeping the ball tract clear of dust and dirt. It is a precision job throughout, of robust yet neat construction, quiet, trouble-free and economical. Delivery is prompt and usually ex stock. We have a range of gear that will do justice to any door you can mention. Our catalogue and leaflets give all the information you are likely to require.



HILLALDAM
A

FOR EVERY DOOR THAT SLIDES

E. HILL ALDAM & CO. LIMITED
The Sliding Door People

HASLEMERE AVENUE, LONDON, S.W.18.

Telephone: WIMbledon 8080 (5 lines). Telegrams: "Aldamillo" Put, London.




His shelter

is cheap enough

TWO NISSEN TYPE SHEDS, SIZE 120' x 30'
SUPPLIED TO :—
STAFFORD ALLEN & SONS LTD.,
LONG MELFORD.

OTHER WIDTHS :—16' 24' & 35'
ALSO BLISTER HANGARS, 91' WIDE,
PROVIDING INEXPENSIVE, LARGE,
CLEAR WORKING SPACE.



THORNS

BUILDINGS too, provide inexpensive shelter

PLEASE WRITE FOR CATALOGUE AND QUOTATION

GIVING DETAILS OR DRAWING OF BUILDING REQUIRED, TO:—

J. THORN & SONS LTD., (Dept. 113), BRAMPTON ROAD, BEXLEYHEATH, KENT

Quickly!

"POILITE"
REGD. TRADE MARK
ASBESTOS-CEMENT
FLUTED SHEETS

"TURNALL"
REGD. TRADE MARK
Asbestos-Cement
CAVITY DECKING
Patent No. 620,012

"EVERITE"
REGD. TRADE MARK
ASBESTOS-CEMENT
RAINWATER GOODS

★ "POILITE" Asbestos-Cement Fluted Sheets used in wall panel construction.
★ "TURNALL" Asbestos-Cement Cavity Decking for light-weight, dry construction roof.
★ "EVERITE" Asbestos-Cement Rainwater Goods for minimum maintenance.

Blurton Farm North School.
J. R. Piggott, Esq., T.D., F.R.I.B.A., City Architect, Stoke-on-Trent.

TURNERS ASBESTOS CEMENT CO LTD

A MEMBER OF THE TURNER & NEWALL ORGANISATION

TRAFFORD PARK

MANCHESTER 17




you can rely on **RAPID**

PRICE & CO. (GLASGOW) LTD., Inchinnan Rd., Renfrew. KINGSTON CONCRETE PRODUCTS LTD., Ryde Ave., Hull. WOOLAWAY CONSTRUCTIONS LTD., Lanelay Works, Pontyclun, Glam.
TARMAC LTD., "VINCULUM" DEPT., Ettingshall, Wolverhampton. JOHN ELLIS & SONS LTD., 21, New Walk, Leicester. RAPID FLOORS (WESSEX) LTD., 17, George St., Bath
THE RAPID FLOOR COMPANY LIMITED, AFRICA HOUSE, KINGSWAY, LONDON, W.C.2. TELEPHONE : HOLBORN 3274

STP Smithson emulsion paint

Architects are invited to write for the
SMITHSON HANDBOOK OF PAINTS & PAINTING PRACTICE
TO THOMAS SMITH AND SON LIMITED
238-240 WHITECHAPEL ROAD, LONDON, E.1.
TELEPHONE: BISHOPSGATE 3717-8-9



NICKEY oak FLOORING

DIGNITY • BEAUTY • DURABILITY • INITIAL ECONOMY
EASY MAINTENANCE • REGULAR AND PLentiful SUPPLIES

Long a favourite in America's design-conscious homes, Nickey Oak Flooring is
now available to British architects and builders.

Ideal for HOUSES • SHOPS • OFFICES • SCHOOLS
HOTELS • PUBLIC BUILDINGS • SHIPS

*For further details apply to your local merchants
or to distributors for the U.K.:*

Denny Mott & Dickson Limited

Adelaide House, King William Street, London, E.C.4

LONDON • LIVERPOOL • PRESTON • GLASGOW • HULL • BIRMINGHAM • CARDIFF • BRISTOL • SOUTHAMPTON
BELFAST

F. H. THOMPSON & SONS SKINNERBURN ROAD • NEWCASTLE-ON-TYNE 4

THE ARCHITECT & BUILDING NEWS

October 11, 1956

The "Architect and Building News" incorporates the "Architect" founded in 1869, and the "Building News," founded in 1854. The annual subscription, Inland and Overseas, is £2 15s. 0d. post paid; U.S.A. and Canada \$9.00. Registered as a Newspaper.

Published by ILIFFE & SONS LTD., DORSET HOUSE, STAMFORD STREET, LONDON, S.E.1.
Telephone: WATERLOO 3333 (60 lines). Telegrams: "ARCHITONIA, SEDIST, LONDON."

Branch Offices: Coventry: 8-10 Corporation Street; Birmingham: King Edward House, New Street;
Manchester: 260 Deansgate. Tel.: Blackfriars 4412 (3 lines), Deansgate 3595 (2 lines); Glasgow: 268 Renfield Street.

WANTED: THE RIGHT SCHEME

ONCE again private enterprise has received a rap on the knuckles. Five town planning applications from private firms for consent to development schemes of railway land at Victoria Station and Approaches have been refused by the London County Council. One scheme is for a multi-storey garage. Two are for large office buildings over the station and approaches. A fourth is for offices, a hotel and flats. The fifth is for an air terminal, including a helicopter landing ground.

The Council, among their reasons for refusal, consider that the merits of road, rail or monorail connections should be thoroughly examined and decisions arrived at before agreement is reached on the establishment of additional terminal facilities at Victoria; and that a helicopter landing ground over Victoria would need most careful consideration.

They welcome in principle proposals for multi-storey car parks, but consider that permission for the present proposal cannot be given before a decision is reached about an air terminal. Where the applications envisage office blocks with considerable increase of employment in Central London (the major question of the future of the air terminal apart) the Council consider it would be wrong to grant permission having regard to the present congestion in the Central Area and the Victoria district in particular. They note that none of the present applications makes any contribution to the solution of road traffic congestion in the vicinity of Victoria where in addition to the main line terminal, there is the District line, the bus terminus for London routes and the long distance coach station. The Council state that they are by no means opposed to redevelopment of Victoria Station and its approaches, but consider that any development should be on comprehensive lines directed towards easing congestion—not adding to it.

It is stressed by the L.C.C. that they are bound to make decisions on town planning applications within a limited period; nevertheless the present refusals can only be viewed as discouraging, to put it mildly.

The L.C.C. have indicated a policy—comprehensive

development—easing congestion—but give little sign of encouraging developers to carry it out. Private enterprise have sponsored unsuccessfully in the past few years a number of large schemes for comprehensive development which have been refused planning permission. How much longer will it be before they lose heart entirely, with so much costly effort going to waste?

And yet have we not the resources to solve London's planning problems? Surely, we have all the information about them in surveys, schedules, reports and documents which have been garnered over the years? Perhaps the greatest need is to reduce traffic congestion and provide adequate shopping centres solely for pedestrians—if only to reduce the daily toll of lives lost on the roads. The London County Council and the Metropolitan Boroughs and the Ministries combined must have all the background information on these two problems amongst others. Private enterprise has given every indication of having both the ideas and the wit to get on with something. Funds are needed to finance any investigation and the solution schemes which are bound to prove costly in themselves. Resources other than public might well play their part here. The spirit which is needed is summed up aptly in the excellent introduction to this year's Nuffield Foundation Report: "Perhaps its (The Nuffield Foundation) methods will be clearer if we think of a foundation as a kind of private bank which finances projects that may yield dividends, not in terms of cash, but of public good. It is a risk-taking bank. It is least interested in secure investments which will produce a modest return. It is out for high dividends and can afford to balance its failures against its successes."

A combined effort would seem the only means of finding solutions to problems London presents. A policy of finding an expediency is more often than not substituted for that of finding a solution. A proper diagnosis is needed; and however unpalatable, the prescribed pill will need to be swallowed in order to effect a cure.

EVENTS AND COMMENTS

UNICEF CHRISTMAS CARDS

It always gives me particular pleasure to mention the United Nations Children's Fund (UNICEF) Christmas cards. Not only because of the good work done by the fund—£81,000 was raised in 1955 from the sale of four and a half million cards—but because the cards are always so well designed. This year there is a charming Steinberg drawing in colour—did you ever see a coloured Steinberg before?—showing the United Nations as a series of bridges linking the continents. There are also five designs by the American artist Joseph Low, in which children's entertainments in various parts of the world are gaily illustrated. Two designs have been given by Jamini Roy of India, and another series of five by Edy Legrand of France is named *Holiday Bound*. These cards can be obtained with or without printed greetings in five languages and in boxes of 10—two of each design—at the very reasonable price of 7s 6d including envelopes.

This year the Fund is supplying a small leaflet to go with each card explaining the work of UNICEF. Cards and further particulars can be obtained from UNICEF (Department G.C.), 14-15 Stratford Place, London, W.1.

CINEPHONE ON THE RADIO

I hear that "The Midland Critics" will discuss Cinephone (see A. & B.N., 24/5/56) on the B.B.C. Midland Regional Programme on Sunday, October 14, at 7 p.m. The chairman will be Gordon Graham, you may remember his Marley-tile-Award talk on South American Architecture at the AA. H. Werner Rosenthal who designed the Cinephone Cinema referred to above will be taking part in the programme.

BUILT IN U.S.A. I.—THE END OF THE STRUGGLE

The opening on time—after postponement—of this important exhibition at the Building Centre is a minor triumph for the tenacity and hard work of the Centre's staff aided by Mr. and Mrs. H. T. Cadbury Brown. I told only half the story last week believing that all the fuss was over. I was wrong.

The two cases of viewers for coloured slides which "attracted" key industry import duty were delivered with the other cases on Monday morning, but the Centre's electricians could not get at them until Tuesday afternoon because the Customs could not give clearance. From the number of telephone calls to and from it seemed that "Stereo Viewers" had the B.o.T. guessing. When the Customs officer eventually came to inspect the cases he had with him written instruc-

tions to seal them up, but, in what is reported as a spirited conversation with his office made it clear that this was a silly idea.

The exhibition is now open and the B.C. would like to forget the last ten days. It seems to me, however, that something is wrong. The B.o.T. and Customs work to a set of regulations and seem to be allowed little discretion in interpreting them. Had the B.C. known about duty-free import licences and duty-free key industry import licences it is possible that the delay might have been less. We should, however, bear in mind that in the first instance the application for a duty-free import licence was rejected by the B.o.T. largely because it was ignorant of the true function of the Building Centre.

It appears that there is no provision in the import regulations for the easy passage of returnable cultural exhibitions. Surely this should be put right. In conversation with an official of the U.S. Embassy I discovered that the same tortuous rigmarole has to be gone through whenever the Embassy wishes to bring in an exhibition. The import of trade films, however, is so hedged in as to be virtually impossible, and this is borne out by the editor of *Metal Industry*, who, reading of the B.C.'s troubles sent a cutting from his paper telling a fantastic story of two films on aluminium offered free by the Aluminium Company of America for showing in this country. The negotiations dragged on for months and although the films were shown to small audiences in a bonded cinema, they were never released.

Although the B.C. insists that the B.o.T. has at all times been most polite and, within its prescribed limits, most helpful, the whole story seems not only fantastic but appallingly wasteful in time, in energy and, indirectly, in money.

Quite rightly, the B.o.T. does not like adverse publicity. Its officials are hardly to be blamed for sticking to the rules. The rules need changing.

II.—THE EXHIBITION

To start with the exhibition is beautifully and simply mounted. There is a minimum of blurbs and a maximum of illustration—some of the photographs are eight feet square. As it happens the colouring of the Centre's smartly remodelled exhibition hall suits the presentation admirably.

The photographs are supported by fifty-nine of these now notorious "stereo-viewers", each containing a coloured slide. I find them somewhat disappointing. They give a 3D effect certainly, but one does not really see the buildings in the round, but in a series of flat planes. The slides themselves are nothing like the best colour transparencies I have seen.

The buildings will be for the most part familiar to anyone who sees the American architectural papers regularly. There is, as always in exhibitions of this highly selective type, a danger that the uninstructed

layman will think that all present-day building in the U.S. is up to this standard. So carefully have the shots been taken that adjoining buildings, even in the heart of New York, hardly show. Here and there a classical detail has managed to creep into a corner of a picture, and this alone serves to remind us that present-day architecture in the States is not all as good as the exhibition makes it seem.

SOME SIMILARITY AFTER ALL

I met Sir Gordon Russell at the private view of the exhibition. He is off to Canada and the States next week and was having a look round so that he could report on the exhibition to its sponsors, the Museum of Modern Art, in New York.

He told me that, like all wise western travellers to the U.S.S.R., he took on his recent visit a roll of toilet paper, some insect powder and a basin plug. In the first hotel he stayed in the basin had seven holes and his flat rubber plug would only cover three of them. In the second hotel the waste was blocked and his plug was unnecessary. Applying for a U.S. visa recently, Sir Gordon, after being finger-printed in the appropriate department of the Embassy in London, was invited to wash. The basin had no plug.

METAL WINDOWS

Some interesting things were said about metal windows by both architects and manufacturers at the first B.C. Forum held last week. Edward Mills attacked the present standard range, the price ring, and rust-proofing, and fittings. Peter Gardener replied with spirit and dealt with the price ring business by contrasting the working conditions in the industry today with thirty years ago and promising everyone a pleasant surprise when the report of the Monopolies Commission on the Metal Window Manufacturers Association is published. Haloes, it appears, will be three a penny. This will be coldish comfort to the architect striving to obtain a competitive tender for standard metal casements from members of the Association. Captain Fox Williams of W. & W., Mr. Attwood, of Crittalls, spoke up loud and often for the member manufacturers and the managing director of Ideal Casements made some points for firms outside. The architects were supported by Mr. A. R. F. Anderson, past president of the AA who complained of damage caused by bad handling of windows on the job. Mr. Mark Modular Hartland Thomas who said that he was sure that before long the manufacturers would have to make a modular range (based on the 4in module, too). Mr. John Eastwick Field and his partner Mr. John Stillman also spoke. In discussion the following emerged. The future of the metal window industry is not in steel or aluminium but in plastics. Zinc spraying and not dip galvanizing are both satisfactory methods of rustproofing but the human element comes on in spraying where it does not in the dip method. Dipped windows can be easily inspected, sprayed windows must be given a pro-

tective coat of paint which covers up any deficiencies in the spraying. The cost of changing over to a new set of standards could not be excessive for manufacturers. The vitrious enamelling of window sections has been considered but a satisfactory enamel has not yet been found. And many other points besides.

I thought this a most valuable evening.

NEW AIRPORT BUILDINGS

Vilhelm Lauritzen, famous as the designer of the Copenhagen Radio House, was in London last week. He has been commissioned to design new terminal buildings at Kastrup, Copenhagen's Airport. The existing building is another of his best-known designs.

Arkitekt Lauritzen spent some time inspecting Gibberd's London Airport buildings and found that, although they appeared to work well in some ways, the Customs and Immigration requirements had seriously interfered with the efficient planning of the building. He considers that when 120-seater aircraft are introduced the one "channel" per aircraft system will break down, mainly because insufficient immigration and customs men will be available to deal with the rush of passengers.

Arkitekt Lauritzen told me that because of the constantly altering methods of passenger handling at airports he foresees a huge open building, preferably without intermediate supports. The interior arrangements being easily changeable.

It is hoped that some other use will be found for the existing terminal building at Kastrup.

A model of Yorke Rosenberg and Mardall's scheme for the new buildings at Gatwick is on view in the hall of the Building Centre. More about it next week.

PARLIAMENT SQUARE

Mr. Duncan Sandys has his eye on Parliament Square and its surroundings. In a letter to the L.C.C. the Ministry points out that the Government is very interested in any development which might take place in the area and asks that the Minister should be consulted on any planning application within or adjoining the area bounded by Great George Street, Storey's Gate, Broad Sanctuary and New Palace Yard. I hope this means that Mr. Sandys will have another look at the Colonial Office buildings.

Particular point is given to the letter to the L.C.C. by another letter this time signed by the Minister himself and addressed to Mr. W. E. A. Bull, the president of the R.I.C.S. It appears that the Institution wants to rebuild on Parliament Square. The Minister points out that the Government is considering the future development of the area, and that he has asked the L.C.C. to consult him. Meanwhile Mr. Sandys suggests that "Your institution may feel disposed to defer for the present their plans for rebuilding."

Could it be, oh! could it be that there is yet a chance of a Westminster pedestrian precinct?

ABNER

NEWS

Saltire Society Award, 1955

The Saltire Society which makes Housing Design Awards annually for good design in Scotland has made its 1955 awards equally in favour of two schemes of flats in East Kilbride (F. C. Scott, Chief Architect) and one in Glenrothes (Peter Tinto, Chief Architect). Success of these two authorities repeats their earlier achievements.

Normally the Society gives recognition to houses and flats. The 1955 completions have not given examples of housing which justify an award and for the first time a group of flats has been treated as equal in merit.

Multi-storey Car Parks for the City?

The Common Council of the City of London decided on Thursday last to seek Parliamentary Powers to provide multi-storey and other garages, together with ancillary facilities in an attempt to offer a realistic solution to traffic congestion in the City's streets. This was done on the recommendation of the committee Court, which concerns itself with the policy of the corporation.

A spokesman of the corporation said there is a strong desire among individual committee members to provide multi-storey garages built either for the corporation or as lettable buildings operated by commercial concerns. However, until the matter was put forward as a concrete suggestion by the appropriate committee, detailed proposals could not be investigated. It is probable that the committee will report more fully in two or three months' time.

Any special authority for the erection of such buildings could be embraced by the City of London Various Powers Act. Until the report is made public it is difficult to know on what lines—construction, car handling, equipment—the buildings might be planned.

Law and Administration

Clean Air

The Clean Air Act, 1956, lays many burdens upon local authorities particularly in regard to the control of domestic smoke. They are given power to create what are called "Smoke Control Zones" but the institution and management of these zones is likely to raise many problems. The supply of suitable equipment, the price and availability of smokeless fuels, the cost of changing domestic installations are all matters which, though by no means insuperable, present considerable difficulties. In controlling smoke emission from industrial undertakings there are another group of difficulties to be found. The way in which these problems are met will exercise a marked influence upon the way in which the powers of the Act are operated and in some cases will decide if they are to be operated at all. Those local authorities and others who are concerned to make the new Act work will find much of value and interest to them in the papers presented last week to the *Southport Conference* held by the National Smoke Abatement Society.

In particular, Mr. D. P. Welman, of the North Western Gas Board, gave some advance details of "Thermalite" which is a smokeless solid fuel. He claimed that this fuel is now in full stage production and the Gas Board hopes it may be available in quantity during this winter. He added that:

"It should be remembered that there are probably up

to ten million houses in the country as a whole which still have a considerable number of years of useful life before them, but which are unlikely for a variety of reasons to be provided at any time in the future with special coke burning appliances. For such houses 'Thermalite' provides an immediate answer without capital outlay on the part of the householder".

Mr. Welman said that the new fuel was clean, easily ignited and easy burning on an open fire. If the claims made for this fuel are correct then the gas industry will have made a handsome contribution to making the new Act really effective in the course of time.

Compulsory Purchase Postscript

It may be recalled [see A. & B. N., 4:10:56] that a complaint was recently made by Lt.-Col. Filkins to the Ministry of Housing and Local Government. He stated that Brighton Corporation had acquired 33 acres of his land for *council housing*. They subsequently resold, for private housing two-thirds of that site, on the terms already reported. Lt.-Col. Filkins applied for permission to build 86 houses on his land claiming that so much of his farm land had been taken from him for building that it was impracticable for him to continue to farm the site in question. The Minister had now dismissed his appeal against the refusal of Brighton Corporation to allow the development, saying that the development would be an undesirable intrusion into open land. The Minister, who hates jargon states that the development would have "consequent detriment to local amenity". Doubtless, there is more to this unusual sequence of events than meets the eye but, upon the face of it, it scarcely seems likely to increase public confidence in the integrity of the administration.

Coming Events

Building Trades Exhibition

October 16-27. The Twenty-first Building Trades Exhibition will be held at the City Hall, Manchester.

The Building Centre

October 17 at 12.45. Lunchtime film show. "The Sliding Door" by E. Hill Aldam & Co. Ltd., at 26 Store Street, W.1.

The Institute of Clerks of Works of Great Britain

October 17 at 6.30 p.m. A lecture on "Reconstructed Stone and Cast Concrete", by T. B. Smith, A.M.I.C.E. Guest chairman: Ronald Ward, F.R.I.B.A. At the RIBA, 66 Portland Place, W.1.

The Royal Institution of Chartered Surveyors

October 17 at 6 p.m. General meeting. Address on "Organization and Planning for Large Building Contracts", by L. J. Holloway, M.I.O.B., at 12 Great George Street, S.W.1.

Victoria and Albert Museum

October 17 at 6.15 p.m. "The Baroque Staircase", by Professor Sir Anthony Blunt, Director of the Courtauld Institute. At South Kensington, S.W.7.

Leeds School of Architecture and Town Planning

October 18 at 7 p.m. W.Y.S.A. Presidential Address, by N. H. Fowler, F.R.I.B.A., and "Criticism of Prize Drawings", by W. T. C. Walker, R.S., A.R.I.B.A. At 43A Woodhouse Lane, Leeds, 2.

Royal Festival Hall Completion Scheme

AT their meeting on Tuesday the London County Council considered a scheme for the completion of the existing Royal Festival Hall, for which an estimate of £35,000 for preliminary expenses was recommended by the General Purposes Committee for approval. The Committee consider it desirable to undertake also further study of the design and cost of the proposed new small hall to be erected between the Royal Festival Hall and Waterloo Bridge.

Royal Festival Hall

It is proposed to extend the unfinished end of the building by 30ft to provide the required back-stage and administrative accommodation and improved access and other arrangements. The principal public entrance will be removed to the new Belvedere Road front, a separate artists' entrance and lift will be provided to the left of the public entrance, and an enlarged box-office and administrative offices, with a small lift affording controlled access to all parts of the building, to the right. Extension of the dance floor and foyers, provision of separate cloakrooms and lavatories, and replanning of the staircases at the lower levels, will enable the public for different functions to be segregated at ground level, and thus permit independent use of the dance floor while a concert is in progress. The present multi-purpose goods and artists' lift will be made available as a public lift at one side of the new entrance, and a second public lift will be provided on the other. These two 60-passenger lifts will provide direct access from ground level, without the necessity of entering the dance floor area, to the

auditorium, the meeting room (at present used for small concerts and recitals), and an enlarged and replanned exhibition suite with bar facilities; and independent lettings of the various parts of the building will be facilitated. At the higher levels, the main bars on either side of the auditorium will be enlarged and adequate accommodation provided for artists, wardrobe and stewards.


It is also proposed to double the capacity of the restaurant on the river front by extending the building 20ft forwards and by filling in the well at the upper restaurant level. This enlargement of the seating accommodation, together with an extension and replanning of the area of preparation for *à la carte* meals, will make it possible to serve an increased public, to offer more varied meals, and to secure a greater use of the restaurant for day-time functions.

At present prices the inclusive cost of completing the existing Royal Festival Hall (excluding the cost of adapting the terrace and of the outside works that will eventually be necessary between the present building and the small concert hall) is estimated as follows: Completion of Belvedere Road end, £615,700; Extension of restaurant, £175,600; Furnishing and equipment, £54,450; total, £845,750.

Proposed Small Hall

The seating capacity of the auditorium would ordinarily be about 1,100 though capable of reduction to a smaller figure, and the stage also capable of reduction by

River front of new scheme.




Royal Festival Hall Completion


screening, would reproduce the orchestra platform in the Royal Festival Hall and thus be suitable for orchestral rehearsals. There would also be an exhibition gallery and other associated accommodation suitable for letting.

South Bank Pedestrian Circulation


Overhead pedestrian circulation will link all the new buildings on the South Bank. This will involve an extension of the terrace in front of the Royal Festival Hall to form a continuous link between Waterloo and Hungerford Bridges, and parts of the work would have to be carried out in association with that of completing the Royal Festival Hall. Extension of the terrace as proposed has been approved in principle subject to the submission of a detailed scheme and estimates.




Site
Plan
Showing
Small
Hall.





LEVEL 64



LEVEL 53





LEVEL 40




LEVEL 01

LEVEL 02

Royal Festival Hall, Belvedere Road front.



LONG SECTION A-A



Above Bar Street elevation

STORE for Tyrrell & Green


SOUTHAMPTON

architects :

YORKE, ROSENBERG & MARDALL

associate architect : J. R. Penoyre

architect in charge : J. S. Snell



SITE PLAN

THE new building occupies an important site on Above Bar Street, and will form part of the East Side of the New Guildhall Square which is to be created in front of the Civic Centre. The site area is 17,500 sq. ft; frontage, 175ft; total floor area, 70,000sq. ft.

Construction was completed in two stages, the first on that part of the site not occupied by a Temporary Store, which had to remain open until completion of Stage 1, the second entailed the demolition of the Temporary Store and the completion of the new building. Stage 1 was started in mid-May, 1954, completed at the end of May, 1955, and opened to the public in early June, 1955. Stage 2 started at the end of May, 1955, completed at the end of May, 1956 and

opened to the public on May 7, 1956. Provisions have been made to extend the second floor over the terrace on the East Park side and to extend upwards one more floor over the whole site.

Planning

The building contains basement, ground, 1st and 2nd floors, and all have sales area. These areas are connected by a spiral chute to the receiving and despatch department in the basement. All goods are received and despatched from the basement which is connected by lifts and chute to a delivery bay at ground floor level on East Park side. The store contains two

passenger lifts, one goods lift, and provision has been made for another goods lift. An escalator runs from ground to first floor level and an extension of this to the second floor has been allowed for. Mechanical plant is placed in the basement and in penthouse buildings on the roof. The whole of the services including the lifts and mechanical plant are concentrated in the South East corner of the building, together with the receiving and despatch of goods. The remainder of each floor is thus left clear for Sales Areas, stock storage, public restaurant, ladies hairdressing, etc., as shown on the plans, pp. 486 and 487.

There are three staircases. The first has open risers, is 6ft wide and runs from the ground floor to the basement sales area. The open stairwell allows views of the basement from the ground floor. The construction consists of boxed steel strings with teak treads suspended from the underside. The second staircase is the main one to the sales area of each floor on the North side of the building and serves also as a means-of-escape. This stair is in terrazzo with precast terrazzo slab treads. Balusters to both these stairs are simple vertical, tubular drawn steel members; alternate members having stainless steel sleeves. The handrails are Teak. The third staircase is for staff access direct to the sales areas canteens, toilets, etc. It is finished in Grano, with quarry tiles on landings, and simple mild steel balusters and handrail.

Elevations

The main windows on all elevations on the upper floors are aluminium, vertically hung sliding sashes in steel frames with a carefully worked out system of wires and weights arranged so that the breaking of a wire will not cause the sudden closing of a sash.

The Above Bar Street frontage has Portland Stone mullions and cornices, with Westmorland slate slabs between windows. On the East Park side the building has Portland Stone mullions and cornices; exposed aggregate concrete slabs and tiling at street level. The elevation at the terrace level is regarded as temporary, as future construction on the terrace will mean carrying the stone mullions and exposed aggregate concrete slabs up one more floor on this elevation. On the third side, Prospect Place, panels are of patterned brickwork and exposed aggregate concrete slabs. Most of this elevation is a party wall, but the adjoining building is not likely to be rebuilt for another 15/20 years.

Other Items

All the shop fitting and interior work, including lighting and decoration was designed by the Clients own specialists. Heating is by means of embedded ceiling panels ("Panelite"); and radiators in some rooms of minor importance. There is complete air conditioning in the basement, kitchen and various other areas. Extract ventilation is used in the Restaurant, Hairdressing and elsewhere. An Automatic Fire Alarm System is installed and connected direct to the Fire Station.



North elevation (above) is detailed on page 488. Sidewalk canopy (below) is detailed on page 489. On the other side of Above Bar Street are some of the temporary shops built since the war. Many of them will be removed to make way for an open space between the East Park and the Civic Centre.



Tyrrell and Green Store

architects:

YORKE, ROSENBERG & MARDALL

quantity surveyors:


RIDER HUNT & PARTNERS

consultant structural engineers:

CLARKE, NICHOLLS & MARCEL


consulting engineers (heating, ventilating and electrical):

Directorate of Building, JOHN LEWIS CO. LTD.




First floor gallery.


Stairs, basement to ground floor.




CROSS SECTION TAKEN THROUGH LIFTS

BASEMENT PLAN





SECOND FLOOR






ROOF LEVEL

GROUND FLOOR

SCALE: 1 IN = 36 FT


FIRST FLOOR







ASBESTOS CEMENT CLADDING
NORTH ELEVATION. SCALE: 1/16 F.S.

Looking west across park.



Cladding on north side.





Tyrell & Green Store

general contractor: Richard Costain Ltd.


sub-contractors:

Asphalt: The Nauchael Asphalt Co. Ltd. Bellustrados (Head): Clarke Hunt & Co. Ltd. Canopy Finishes: H. N. Barnes Ltd. Ceilings (Suspended): Brackley, Conserving & Lathing Ltd. Cladding (Light steel to Excelsior): W. T. Allen & Co. Ltd. Demolition: Henry Osman & Co. Ltd. Display Windows: H. N. Barnes Ltd. Dome Lights: T. & W. Ide Ltd. Doors: F. Hills & Sons Ltd. Electrical Installation: F. H. Wheeler (Southern) Ltd. Fire Alarm System: Associated Fire Alarms Ltd. Flooring (Rubber): Cellulose Flooring Co. Ltd. Floors (Wood Strip): The Acme Flooring & Paving Co. (1904) Ltd. K. W. Brooks Co. Ltd. Glazing: E. A. Hilderson Ltd. Joinery: Harry Serravallo Ltd. Ironmongery: Alfred G. Roberts Ltd. Joinery: Golding & Ansell. Kitchen Equipment: Banham & Sons Ltd.

KEY DIAGRAM

CANOPY DETAILS SCALE: 1/8 F.S.

Lifts and Escalator: Waygood-Otis Ltd. Melting (Rubber Link): Nuvay Manufacture Co. Ltd. Paints: Arnold Shorrocks Ltd. Paving: L. Land Pavilion Co. Ltd. Co. Ltd. Partitions (Office): Compascon Ltd. Piling: The Cementation Co. Ltd. Plumbing, Drainage & Cold Water Supply: Richard J. Audrey Ltd. Roofing: Wm. Briggs & Sons. Sanitary Fittings: Shanks & Co. Ltd. Scaffolding: Scaffolding Co. Ltd. Shutter (Rolling): Haskins. Signs (Illuminated): Signacrafts Ltd. Slabbing (Concrete): Costain Concrete Co. Ltd. Slate: Satchell & Sons Ltd. Spiral Chute: Sovas Ltd. Staircases: Clarke, Hunt & Co. Ltd. Steelwork (Structural): Power & Deane. Stone: Stone & Sons Ltd. Scaffolding: Scaffolding Co. Ltd. Strongroom Door: Chrysothem Ltd. Tiling: Wiggins-Sankey Ltd. Windows: (Metal): Williams & Williams Ltd.




Solar House

at

RICKMANSWORTH

Mural and staircase by night; both by Cecil Stephenson.



architect : EDWARD J. W. CURTIS

AN elevated and sloping site, overlooking the Colne River valley at Rickmansworth, was chosen for this house in order to take full advantage of the South aspect for using Solar radiation experimentally. The house shows that the narrow fronted plot can be well exploited, bearing in mind that the majority of house owners require ease of access for transport, shopping facilities, schools, etc.

Permission to build was refused by the Chorleywood U.D.C. on the grounds of incompatibility with surrounding property. Rickmansworth U.D.C. also opposed the project on the grounds that it would make similar designs possible in their area. After a public inquiry approval was given by the Minister of Housing.

Environment

The lower level of the house (except for entrance hall and cloakroom) is virtually one space, subdivided only by a kitchen fitment and partitions 6ft 6in in height between kitchen-play area and dining-living area. A shaped top swivelling on tubular steel column acts as a "door" for service and access to and from the kitchen.

The internal sense of space is increased by placing the sitting area on a lower level and opening part of it through the first floor. The main bedroom becomes a balcony overlooking the living room; a glass wall to the second bedroom also overlooks the void. The ceiling heights are dining, kitchen, hall, etc. 7ft 6in; sitting area 8ft 6in and void 16ft 9in.

A free standing fire, for psychological reasons, forms a focal point at the change in floor levels. It has a circular concrete stack, coloured citron yellow which can be seen both indoors and from out as it penetrates through the balcony bedroom to the roof. The stack weighs 1½ tons, is carried on a reinforced slab cantilevered from a curved concrete wall, is textured on top with large coloured beach pebbles, ammonites, etc., and terminates in a circular water channel. Fire tray incorporating under floor draught and hood with throat controls are both in polished steel.

Light is distributed internally from three window wall panels (one at each end and a side panel). It was found possible, after tests on a model, to eliminate all other windows except for two small ones in bedrooms.



Main south elevation overlooking Colne Valley ; in rain at night.

*Side window wall panel with door to
play space and kitchen.* ▶

Mobile Colour Scheme

The inner skin of the side walls (white-grey facing bricks) and the double glazed south window wall are integrated with a mobile colour scheme produced by curtaining which is hung on double white nylon tracks. The curtains return on the side walls at both floor levels, so that a giant abstract pattern is formed capable of infinite variations when used in conjunction with semi-transparent curtains for sun diffusion which are hung on a second track. Curtains used are: Persimmon to double height void; Black Windsor to balcony bedroom; an abstract, Raw Coral, in white, Persimmon and black to sitting area; yellow and black Texturenet on second track. Curtains were chosen in collaboration with Mr. Tibor Reich.

The window wall externally is painted white with black opening lights and yellow Vitroslab spandrel panel, which reads with curtains to form an exterior colour pattern. Accoflex flooring tiles—black to living area and grey-white elsewhere—have been selected in relation to the colour-light process described above.

Flexibility is obtained on the ground level by removable partition to play area and curtains (Stratford Purple) between living and dining areas which are used also in conjunction with the main curtaining scheme,





Entrance elevation ; heat exchanger on garage roof and incised line abstract by the architect.

consulting engineer :

S. A. BRADBURY

general contractor :

J. E. AMBRIDGE & SONS LTD.

sub-contractors :

Blinds :

J. Avery & Co. Ltd.

Ceilings :

Celotex Limited.

Curtain Track :

Swish Products Ltd.

Curtain Material :

Tibor Reich

Double Glazing Units :

Plyglass Ltd.

Electric Fittings :

Simplex Electric Co. Ltd.

Flooring "Accoflex."

Armstrong Cork Co. Ltd.

Heat Pump & Air Conditioning :

Denco-Miller Ltd.

Insulation :

Alfol Insulation Ltd.

Light Fittings :

Coombe Products.

Paint :


Permoglaze Ltd.

Partitioning :

The British Plaster Board (Manufacturing) Ltd

PLANS

SCALE : 1 IN = 16 FT



House at Rickmansworth

already described. Entrance hall, cloakroom and landing, to North and facing the road provide, in conjunction with the double glazed window wall, a barrier at the "cold" end of the plan. The double glazed Plyglass screen, between dining and hall, with diffusing slats of glass fibre, cuts off the view in from the road; the slats pick up the outline of the staircase and create moving shadow patterns on floor and walls, as the sun moves round to West.

The staircase has a light welded steel framework carrying shaped treads in natural beech with Royal Blue Axminster insets. The balustrading is $\frac{1}{2}$ in diameter polished steel rods and the handrail is in natural beech. An abstract mural (10ft 6in by 7ft 6in) on the inner staircase wall is a spatial design seen externally; it contrasts with the mechanical structure, and picks up staircase and wall colours. The mural was executed by Cecil Stephenson, who also constructed the staircase.

Upper Level

Flexibility has been aimed at on the first floor by the following arrangement: the display space at the landing end, lit by high level lights in the window wall, will normally be used for the display of pictures and sculpture by artist friends. It is possible to curtain off this area for use as a sleeping space.

Access to the balcony bedroom provides studio space which can also be used for temporary sleeping. The two small bedrooms are divided by removable storage fitments, so that a single, or partly divided space, can be formed. Later, a room can be added over the garage with access through the display space. The bathroom, which is seen as a dark blue free standing cube from landing and studio, incorporates a hot air linen drying or airing cupboard fed from the heat pump rising hot air duct.

All trims to floors, door frames, plinths, framing to cupboard fitments, etc., are finished matt black and all

doors, fitments and screens, etc., are in natural mahogany or gaboony faced plywood with wax finish.

Proportional Control

The external rhythm of fenestration and spatial organization internally is controlled by the golden diagonal of proportion, the large window walls being made up in each case of two G rectangles, with opening and fixed lights transferring this proportion to a smaller scale; the garage block is also placed in relation to a main diagonal.

Internally the dining and living area and related surfaces are G rectangles and the proportion is repeated vertically in the void. Initial sketch scheme took no account of the Golden Mean but it was found that by very little adjustment the proportional scheme could be applied.



Atmosphere Control

The architect felt that too little attention has been given to providing complete atmospheric control of domestic environment by electrical power, and also that the vast potential of solar heat and energy must be harnessed as part of the New Technology, therefore it was decided to create an experimental framework which would incorporate: 1. An air to air heat pump installation giving complete air conditioning, hot water and refrigeration backed up by 2. Solar reflecting screens; 3. A kinetic Solar panel.

Air Conditioning

Year round air conditioning is provided by an air to air heat pump. During winter months heat is extracted from a heat exchanger on the roof of the garage. This heat is collected, raised to a higher temperature level and given up to the house. During summer months the system is reversed and heat is absorbed from the building and given up to the outside heat exchanger. A small room (5ft 6in by 4ft 6in by 7ft 6in high) is set aside for the main unit and heat pump equipment. The equipment, apart from the outside heat exchanger, which is piped to the main unit, is self contained and totally enclosed within a metal cabinet.

The fan for circulating the conditioned air is located within the cabinet and draws air first through a filter





Bedroom looking towards void and road.

House at Rickmansworth

and then through a heating-cooling coil, according to the season, before delivering the air through the ducting. Hot or cold air, treated as above, is circulated by a simple ducting system formed between first floor joists and by insulated metal ducting in the roof. These ducts are served by a main rising duct which houses all vertical hot and cold water pipes and also provides hot air for linen drying or airing.

Plastic diffuser cone outlets with individual control are set flush with ceilings and used air is extracted at ground level, via staircase and living room void, by an under floor duct which returns stale air to a machine in the Heat Pump for cleaning, etc., and recirculation.

The maximum capacity of the plant is 36,000 B.T.U./hr and the fan delivers 1,000 CF.M. Average discharge temperature is 90 degrees F. Output on the reverse cooling cycle is 30,000 B.T.U./hr. Considerable dehumidification is accomplished in the process of cooling. The unit is automatic in action and is controlled from a thermostat installed in a control panel in the kitchen. The estimated running cost in the winter season is in the region of £18.

Water Heater and Refrigerator

Domestic Hot Water and Refrigeration are provided by dual purpose heat pump. The unit, which is in two parts, i.e. refrigerator and water heater, represents the latest advance in the application of the heat pump for domestic use. The refrigerator is of the built-in flush mounted pattern, with a nominal capacity of 6 cubic feet and the usual ice making compartment and tem-



perature control thermostat. The water heater is located in the heat pump room, with the large unit as described. Heat energy from the air in this room is absorbed by the appliance, regenerated at a higher temperature and given up to the water which is controlled by a thermostat at 140 degrees F. The unit is powered by a $\frac{1}{2}$ -h.p. sealed compressor integrally mounted within the water heating generator, but separated from the water. Projective switchgear guards against the possibility of damage to the compressor by overloading. The unit will provide up to 120 gallons of hot water per day for an electrical consumption of only 10 KW; the refrigerator does not consume any additional energy. The heat absorbed from the refrigerator compartment is added to the water and is generally sufficient to make up the heat leakage losses from the tank and pipes, etc.

Solar Heat



The Solar reflecting screens which flank the Terrace and pool on the East side, will have polished aluminium faces and will be adjustable for sun travel. These will be used at a later date, with a Solar panel on the internal wall face to the void. The panel (16ft 0in by 11ft 0in) will contain a heat retaining medium and will be used in conjunction with the main heating installation.

A basis for scientific study has been provided and temperature tests, etc., have already been instigated as a preliminary step to ascertaining the comprehensive effect of all systems. The Eastern Electricity Board are co-operating by installing meters to check all units, cooking, lighting, etc., on a day/night basis.


Continued on page 496








SECTION D D



Living area towards position of future solar panel. Fireplace detail. Scale: 1 in = 1 ft.





WINDOW PANEL DETAILS. SCALE: 1 IN = 1 FT

House at Rickmansworth

Thermal Insulation

To gain full effect from the air conditioning system heat insulation is provided for by clear cavity, Plyglass and Vitroslab backed with Asbestolux to all window walls. An aluminium foil "wrapper" is hung centrally in the 3in wide cavity to load bearing walls, and is continued over the roof space. Over $\frac{1}{2}$ in Celotex ceilings are three layers of Crumple foil, plus a top layer of heavy duty foil. Celotex and 1in fibreglass are placed under the first floor. Cavities to resin bonded panels on the north window wall are insulated with two webs of heavy duty aluminium foil giving three air spaces.

Building Sequence

In an attempt to cut building costs and to speed up erection time, the basic framework was built in the following way. Ground floor slab was laid including extract ducts for air conditioning. From side foundations only, two longitudinal load bearing cavity walls of Hamhill Brunswick outer skin and Midhurst White inner skin, stiffened at ends with piers, were constructed to roof level. The first floor of 9in by 1 $\frac{1}{2}$ in joists was stiffened longitudinally at clear span by a 4in by 3in steel web supported on 2in diameter steel columns, one being utilized in the living area for light fittings, and the other to take swivel serving top in the kitchen. The corner of the balcony bedroom and the landing are supported on columns also.


As the walling proceeded the complete aluminium foil "wrapper" was hung centrally from wall ties in the 3in wide cavity; horizontal laps were sealed with Bostic. Various operational methods were tried out to reduce labour time and proved most valuable.

With the walling completed, timber roof trusses at 2ft 0in centres and of 22 degrees pitch were then positioned and covered with boarding, felt, battens, counter battens, and finished with grey Marley interlocking tiles.

Timber window wall panels for ends and side on a 3ft 4in module and basically of 5in by 2in main members, fabricated off site, were then fixed in position by 4 men in 4 days and double glazed or panelled. Parallel with these operations, the reinforced concrete fire slab and stack were cast and the first floor laid together with heat pump ducts between joists. The building then became a closed box with completely free space on both floors. Paramount partition units were next erected on the first floor in conjunction with floor to ceiling door frames; and $\frac{1}{2}$ in Celotex ceilings were fixed to both floors, enabling emulsion paint to be immediately applied.

Copper service pipes and internal single stack plumbing unit, with connections and metal ducting and aluminium foil insulation in the roof were now completed; and ground floor slab screeded and covered throughout with Accoflex tiles. Kitchen fitment, fixed and removable timber partitions, sink unit framing

Staircase: Welded metal framework with beech treads and handrail.



Heat pump room showing equipment being built in.



Kitchen showing built in refrigerator and air conditioning control panel.

and glazed screen on ground floor, storage fittings for first floor were positioned next, all having been fabricated off site. All joinery work was delivered complete in sequence, ready to fix, making full use of machine techniques and reducing site work.

Refrigeration unit was built into prepared framing with heat pump compressor and air conditioning unit positioned in heat pump room.

Times and Cost

The building was completed in 5½ months of winter weather and the contractor estimates that this time could be cut to four months by experience gained on the prototype. The total cost including garage, double glazing and ducting but not including site works or actual heat pump machines is likely to be under £4,000 when final figures are obtained.

LEGAL COMMENTARY

"Statutory Safety Requirements"

By F. H. B. LAYFIELD

THE common law duty imposed upon an employer to provide safe conditions of work for his workpeople was discussed in the last *Legal Commentary*. Mention was also made of the fact that, in addition, the employer must comply with certain statutory requirements. Unlike the common law these requirements are not based upon any general principle, and they do not form a code. Each statute, and even sometimes each regulation made under the powers of a statute, provides its own special rules and sets out its own definitions and tests. This presents the employer with the difficulty that he must discover whether each and any particular statutory requirement applies to the work he has in hand or to the place where that work is to be done. On the other hand once he has ascertained that, say, a regulation applies to the work he is doing then it is often easier to say with certainty what precautions will, if adopted, meet the demands of the statute than is the case with the common law. But if the two realms of law are different in some aspects they are not entirely separate or distinct.

Statutory Liabilities

A breach of a safety requirement created by statute is almost always an offence for which the appropriate authority may prosecute the offending employer. It is natural to ask therefore, if an employer is in breach of a statutory duty for which he can be prosecuted, can an injured workman also make a claim against him upon the same ground? This question was answered in detail by the House of Lords this year when they gave judgment in *Grant v. National Coal Board*. Lord Simonds said that:

"Where damages are claimed for breach of a statutory duty without any allegation of negligence, the... [claimant] must establish two things: first, that the breach is intended, not only to be visited by a penalty, but also to be the ground of civil liability to a class of persons of whom the... [claimant] is one, and, secondly, that the injury was one against which the legislation was designed to protect him."

This statement raises, in turn, the question of how can the injured person show that breach of the statutory duty was intended to give him a right of action. This was answered by Lord Reid giving judgment in the same case when he said:

"The question whether an employer is liable to an employee for injuries caused to him by breach of a statutory duty depends on whether there can be implied from the terms of the statute imposing the duty an enactment that the employer shall be so liable. In general that is implied from the enactment of a duty in the interest of the safety of employees..."

Lord Keith also made it clear, in his judgment, that the workman is not in any way debarred from his claim because he may be able to rely upon a breach of another statutory obligation. Referring to the Act involved in this particular case, Lord Keith observed that:

"I can deduce from the language used only that the section was passed for the protection of workmen and that if a workman is injured by a breach of the statute he has a remedy in damages against his employer. There may

be some other statutory provision or regulation, on which he can rely, but there is no reason why protective provisions may not overlap, and it is common experience to find an injured workman relying, sometimes successfully, on breach of two or more statutory provisions or regulations."

One limitation to the employer's liability which must be borne in mind was mentioned by Lord Reid. It arises in this way. If a statute imposes a duty for a particular purpose and there is a breach of it will the employer still be liable if a wholly unrelated kind of damage occurs? This was what happened for example in *Gorris v. Scott*. There the purpose of the statute was to prevent the spread of contagious disease in animals and, in a ship, pens were required to segregate animals for this purpose. The pens were not provided on this occasion and, as a result, some sheep were washed overboard and lost. If there had been proper pens this would not have happened. It was held there was no liability because the purpose of the enactment was to prevent the spread of disease and had nothing to do with safety. Having reviewed these facts, Lord Reid continued:

"I do not doubt that the case was properly decided; if the enactment implied civil liability at all, then the appropriate implication was liability if a breach caused or contributed to a spread of disease. But it seems to me to be a very different thing to say that, where the object of the enactment is to promote safety, the implication is that liability only arises if the breach causes injury in a particular way. I do not think that there can be any general rule. In every case the problem is to ascertain the intention of Parliament from the terms of the statute—whether any and, if so, what civil liability is to be implied."

There are, of course, instances where the Act or the Regulations concerned are clearly designed to deal with a particular kind of damage. Only in such instances will it be insufficient to give a right of action to show that breach of the relevant duty has led to a type of injury different from that anticipated by the legislation concerned. For, as Lord Reid stated:

"If the statute is only aimed at preventing a certain kind of injury, then it seems reasonable to hold (as in *Gorris v. Scott*) that civil liability only results if that kind of injury is caused by a breach."

It will be noted that in such instances, the mere fact that a breach of a statutory duty does not cause the particular kind of injury at which the statute is aimed does not mean that the employer is not liable to prosecution for the breach even though he may escape civil liability.

The Onus of Proof

It is, of course, not sufficient for a workman who has been injured merely to show that there has been a breach of statutory duty; nor only to show that he has been injured. The onus of proof on the injured workman is substantially the same in the case of a breach of statutory duty as at common law. What the workman must show was clearly described by Lord Reid in a case heard by the

House of Lords earlier this year. Giving judgment in *Bonnington Castings Ltd. v. Wardlaw* he remarked:

"It would seem obvious in principle that a . . . plaintiff must prove not only negligence or breach of duty but also that such fault caused or materially contributed to his injury, and there is ample authority for that proposition both in Scotland and in England. I can find neither reason nor authority for the rule being different where there is a breach of statutory duty. The fact that Parliament imposes a duty for the protection of employees has been held to entitle an employee to sue if he is injured as a result of a breach of that duty, but it would be going a great deal further to hold that Parliament intended that any employee suffering injury can sue his employer merely because there was a breach of duty and it is shown to be possible that his injury may have been caused by it. In my judgment, the employee must in all cases prove his case by the ordinary standard of proof in civil actions; he must make it appear at least that on a balance of probabilities the breach of duty caused or materially contributed to his injury."

"Persons Employed"

It follows from what has been said that an injured workman, if he alleges breach of statutory duty, will often have to show that the relevant precautions are required for his protection. Some useful and interesting observations were made in this connection in *Massey-Harris-Ferguson (Manufacturing) Ltd. v. Piper*. In that case [reported A. & B.N., 12.7.56] a man employed by a firm of painters and decorators was painting in a factory when he came into contact with the supply lines to an overhead travelling crane and was electrocuted. It was alleged by the factories inspector that there was a breach of the Electricity (Factories Act) Special Regulations, 1908. As against this it was contended by the defendants that these regulations were made only for the benefit of the servants of the occupier of the factory, a class of persons which did not embrace the deceased man. Dealing with this point as regards these particular regulations the Lord Chief Justice described the attitude of the court.

"I think there is no question about it that these regulations now are intended to protect, not only the servants of the factory occupier, but any other persons who may be called upon to do work in the factory, such as sub-contractors. These are the type of people who particularly need protection. They are not accustomed to the work of the factory, they do not know anything about the working of these electric cranes or the details of the electrical installation in the factory. Therefore, it is all the more important if outside contractors are employed—and the appellants appear to do all their maintenance work by means of outside contractors—that they should be protected."

It is, perhaps, noteworthy that Mr. Justice Streatfeild who also gave judgment in that case, agreed with the decision of the Lord Chief Justice, and added:

"I am all the more glad to be able to reach that conclusion because it is particularly important that safety regulations should be observed for the employees of contractors who may be only occasional workmen in a factory . . ."

Dangerous Machinery

One of the most common sources of anxiety to employers and particularly contractors are their duties in regard to machinery. There have been a number of cases this year which have helped to make clear the way in which some Acts and regulations operate. The most pervasive and,

perhaps, important enactment of this kind is the Factories Act, 1937. A case early this year dealt with the operation of Section 14 of that Act. That section provides, among other things, that "every dangerous part of any machinery, other than prime movers and transmission machinery, shall be securely fenced . . ." It was alleged in *Bullock v. G. John Power (Agencies) Ltd.* that the employers had neglected to comply with the requirements of that section. The plaintiff had been killed by material in a machine escaping and striking him (in this instance it was wire under pressure). It was said that the wire was "a dangerous part of machinery" and should have been securely fenced. Now the section also provides that "The Secretary of State may, as respects any machine or any process in which a machine is used, make regulations requiring the fencing of materials or articles which are dangerous while in motion in the machine." These are important words for as Lord Justice Denning pointed out "the section itself draws a distinction between parts of machinery, on the one hand, and materials or articles which are in motion in it on the other hand." Giving judgment, he continued:

"The truth is that the whole piece of wire was being worked on in this machine . . . It was material in the machine and not part of the machinery. The Act does not require material to be fenced. It is left to the common law . . . and the plaintiff not having proved negligence at common law the action must fail and she must be left to her remedies under the industrial insurance provisions."

The Court of Appeal came to exactly the same conclusion in the case of *Kilgollan v. William Cooke & Co. Ltd.* which was mentioned in the last *Legal Commentary*. The employers were held not to be in breach of their statutory duty because the dangerous thing was material ejected from the machine and not a part of the machine. The vital difference between *Bullock's* case and the *Kilgollan* case was that in the former no similar accident had ever been experienced before in the factory, and there was, accordingly, held to be no negligence at common law, while in the latter case there had been repeated similar accidents and it was considered that there had been negligence.

Another exception to the requirements of Section 14 of the Factories Act, 1937, was discussed in *Stringer v. Automatic Woodturning Co. Ltd.* In this instance the plaintiff, a young girl, had been injured by a circular saw. It was alleged that the saw, being a dangerous part of a machine, should have been securely fenced. On the other hand it was admitted that the saw was equipped with protective devices which were exactly as prescribed by Regulation 10 of the *Woodworking Machinery Regulations, 1922*. These regulations are deemed to have been made under the Factories Act, 1937 (by virtue of Section 159 of that Act). The vital question was this: was the requirement of the Regulation or that of the Section to prevail. Lord Justice Jenkins, having reviewed the case which dealt with the relation between the Factories Acts and regulations made under those Acts, decided that:

"The plaintiff cannot succeed on the ground of breach by the defendants of their statutory obligation to fence under Section 14 of the Factories Act, 1937. These cases seem to me to provide clear authority for the proposition that the obligation of a special regulation, such as Regulation 10(c) of the *Woodworking Machinery Regulations* in the present case, where such special regulation has been duly complied with, is to be regarded as substituted for the more general obligation as to fencing contained in Section 14 of the Act."

Lord Justice Singleton put the same view in another way when saying that:

"In the present case we are dealing with a circular saw,

Statutory Safety Requirements

and with nothing else. But for the regulations, Section 14 of the Act would have applied. If the regulations apply to the saw they *modify* the obligation of the employers. The employers fulfilled their duty in regard to the circular saw if they provided that which they had to provide under the regulations as a guard for the circular saw . . ."

Yet it must not be thought that the matter necessarily stops there. As Lord Justice Hodson pointed out in this case.

"The position of the Court I think is this: Although in many cases where dangerous operations are covered by regulations, compliance with the regulations would absolve an employer from liability in the case of accident, yet the Common Law is not helpless to fill up gaps, because the duty of the employer remains. The duty is not to expose his employees to unnecessary risk, and that duty is not ousted by regulations."

A further difficulty may be involved where compliance with statutory provisions is concerned as appears from the case of *Quinn v. Horsfall & Bickham Ltd.* Here a man was working on a metal milling machine when he was injured. That machine was fitted with a guard but the guard did not satisfy the requirements of Section 14 of the Factories Act, 1937. The defendants' reply was that the *Horizontal Milling Machines Regulations, 1928*, applied, and therefore the provisions of those requirements were to be substituted for those of the section.

"The result of the . . . Regulations . . . is that when the cutters on milling machines are being used other than for the purposes referred to in the exemptions those cutters must be fenced in the way laid down by Regulation 3."


Had the matter ended there, doubtless, the employers would have been safe. But one of the exemptions was that Regulation 3 was not applicable to cutters used for "automatic profiling" which was the job the plaintiff was doing when he was injured. Furthermore the regulations also contained a proviso which, said Lord Justice Morris, meant in this context that "the exemptions shall not prejudice the application of Section 14 in regard to the fencing of such cutters, namely, cutters that are being used in one of the exempted processes."

Thus by means of an exemption to the regulations the duty of the employer reverted to observance of Section 14. As that section had not been duly observed there was, accordingly, held to be a breach of statutory duty.

Summary

Many safety requirements which must be observed, not only in factories and workshops but on building sites and elsewhere, are now the subject of statutes and of regulations made thereunder. In order to decide whether any of these statutory rules apply to a particular case it is necessary to refer to the actual enactment for its terms. A breach of duty so imposed will normally render the employer, or sometimes the person in charge of the site or premises, liable to prosecution. This liability is of course, regardless of whether an accident has occurred as a result of the breach or not. If an accident should occur then the persons injured may be entitled to sue the employer, in addition to the employer's liability to prosecution, provided certain conditions are satisfied. These conditions include two of prime importance; in the first place the workman must show that he is a person for whose safety and protection the relevant precautions were made obligatory and, secondly, that he belongs to a class of persons to whom the Act concerned was intended to give a right of action. This latter condition is usually satisfied, by implication, if the enactment concerned clearly is made for the safety of the relevant employees. If these conditions are satisfied the employee will probably still have a right of action even if the injury which has occurred was not precisely the kind of injury likely to have resulted from that particular breach of duty, *unless* the statute is clearly only aimed at preventing a particular class of injury of which the injury concerned is not one. The injured person in order to succeed must show not only that there has been a breach of statutory duty but also that the breach in question caused or materially contributed to the injury of which he complains, or at least that this is so on a balance of probabilities.

If an employer is put under a duty to take precautions by the provisions of a section of an Act, it is always important for him to ascertain whether he has discharged or avoided that duty if he complies with relevant detailed regulations made under the same Act. Each case will need to be examined on its individual facts and it is not safe to say more than this: the employer should be aware that if regulations apply to a machine or an operation then it is likely that those regulations are in substitution for, and not in addition to, the more general requirements of the Act under which those regulations were made. Care must also be taken to ensure, though regulations may apply generally to a machine or an operation, that there are not exceptions or exemptions which throw the employer back upon the more general requirements of the parent Act.



Perspective of Gavrelle House now being built at 2-14 Bunhill Row, E.C.1. Due for completion at the end of '56 it has 63,000ft sq of office space and a basement car park. Street frontage is 380ft with a similar length at the back facing the Hon. Artillery Co. ground—a permanent open space. Architect: A. G. Paton. Contractors: Bernard Sunley & Sons.

Information Digest

OFFICIAL PUBLICATIONS

- **British Standard Specifications**, from British Standards Institution, British Standards House, 2 Park Street, London, W.1. Telephone: Mayfair 9000.

B.S. 874 : 1956. Definitions of Heat Insulating Terms and methods of determining thermal conductivity. Price 5/-.

B.S. 1244 : 1956. Metal Sinks for Domestic Purposes. Price 3/-.

B.S. 1329 : 1956. Metal Lavatory Basins for Domestic Purposes. Price 3/-.

B.S. 1763 : 1956. Thin P.V.C. Sheeting (Flexible, unsupported). Price 10/-.

B.S. 2739 : 1956. Thick P.V.C. Sheeting (Flexible, unsupported). Price 6/-.

B.S. 874 is a clarifying and co-relating document which has its value for those specializing in heating and insulating matters so is not primarily of interest to the architect and builder necessarily restricted to close approximations. Where products from abroad are being considered whose thermal values are described in unfamiliar terms or whose values differ from those in this country conversion tables are provided. The "joule" is now adopted as the fundamental unit of heat as in B.S. 350: 1940, Amendment No. 4, October, 1953 (P.D. 1715), defining also corresponding values for the revised "steam table British thermal unit" and revised steam table calorie. These changes are stated to have negligible effect on insulation calculations. Of particular importance is the revision of the methods of measuring conductivity, thermal conductance and thermal transmittance of heat insulating materials.

B.S. 1244 covers sinks in stainless steel, enamelled pressed steel and enamelled cast iron. Requirements for resistance of enamel to abrasion, acids and alkalis are given. Overall sizes remain unchanged so as to allow of interchangeability, but minimum bowl sizes now laid down allow some flexibility in detail and design. Single sinks without draining boards are no longer covered. Positions and types of wastes are allowed greater freedom. B.S. 1329 deals with parallel changes relating to lavatory basins in stainless steel, enamelled pressed steel and enamelled cast iron. Requirements for resistance of enamel to abrasion, acids and alkalis are given. The overall dimensions for the metal sinks are similar to those for ceramic ware. Details are also given for pedestals, while the basin design allows for the use of taps, wastes and brackets to appropriate B.S.

B.S.S. 1763 and 2739 describe the quantities required as to permanence of dimensions, colour, pattern, print and flame resistance of sheets from 0.004in to 0.35in thickness and their tear strengths. With the interest in these as wall coverings and upholstery materials the issue of these is of importance. All conforming are required to be labelled as to manufacturer and to bear the kite sign.

- **Building Research Station Digest No. 91. August 1956. The Programming of House-building.** H.M.S.O., price 3d.

A properly balanced labour force is clearly fundamental to a well-organized building contract. This digest shows how time can be lost through shortages in trades by charting the manhours needed for a pair of semi-detached houses. The various operations from taking over a vacant site to completion have been examined, and a "master" operation in each of four stages in construction noted.

The trades have been analysed as to manhours needed for the houses, e.g., general labourers 490, bricklayers and labourers 1,100, in the aggregate, while these totals can be broken down to individual targets by dividing by the number of operatives in each trade. Comparisons are given of balanced and unbalanced forces thus:

| | | |
|----------------------------------|---|----------------|
| Unbalanced | | |
| 4 general labourers @ 122 | = | 488 manhours |
| 3 bricklayers, 2 labourers @ 220 | = | 1,100 manhours |
| Balanced | | |
| 5 general labourers @ 98 | = | 490 manhours |
| 6 bricklayers, 4 labourers @ 110 | = | 1,100 manhours |

The key trade in the houses examined was bricklaying so the doubling of the bricklaying and associated labourer force shortened the time in days for this work so avoiding unproductive time for plasterers who in both cases only took up 330 manhours. The time cycle, through properly balanced trades, was consequently just about halved. On such small jobs it is evident that some unproductive time must be expended but the periodic coming and going of trades engaged during one contract can be much reduced.

The digest also suggests creation of teams to do specific works repeated in houses in turn. Repetition results in the members gaining speed and working more co-operatively while parallel gangs on similar jobs may be influenced by competition to seek to improve their achievements.

The digest suggests that a Progress Engineer should be engaged on large housing contracts to supplement the Agent, with the duty of ensuring a steady flow of material to all trades, getting scaffolding erected at the right time and by varying the manpower of gangs to suit emergency conditions as they arise. Suggestions are given for analyzing the work graphically, as by marking the elevational drawing with areas representing a day's work by the bricklayers and which enable losses and gains on the programme to be seen quickly. This suggestion is illustrated in the first Figure, while Fig. 2 gives two stages in the form of a Progress Chart based on skilled and unskilled trades, working days and sequence of operations up to laying of oversite slab. Fig. 3 gives the form of the Progress Chart for bricklayer and carpenter above d.p.c. while Fig. 4 gives the same information for finishings and including plumber and electrician. Each Chart is analyzed into gangs and number of operatives in each trade.

The Progress Charts are more detailed than is customary, at any rate in the presentation and should result in unbalance in the early stages of continuing housing contracts to be noted and adjusted. The unpredictable effect of uncongenial weather is referred to in the suggestion that a day or two be added here and there to allow for delays but these can affect one trade much more than another—e.g., final site works while painters are still at work internally—which could throw the programme out of gear.

- **Timber Industry in Europe 1955. A Study by the Timber Committee of O.E.E.C.** H.M.S.O., price 11/-.

O.E.E.C. annually examines a number of industries and its reports cover markets during the past year and trends forecasting the future. The past year has continued for expansion of the market in sawn softwood and pulpwood, despite increased prices and restrictions, partly due to rises in freight charges but meeting with some resistance from government and trade consumers.

Information Digest (continued)

There is some concern about the future of the trade in sawnwood and propaganda campaigns for increased consumption are contemplated; not the least worrying factor being the growing elimination of sawnwood by substitutes and alternatives, as in house construction where no wood whatever need be used in some patented designs. Another instance cited is the development of metal and plastic skis—both these are probably insignificant in themselves but show the trend of invention. Propaganda is therefore to be based on technical and economic arguments.

The report is one for the timber trade and economist but points are made, as for example in the references to the uses of sawdust and shavings, which show that declines in some markets may be more than balanced by the invention and development of new wood-base products.

TRADE ASSOCIATION PUBLICATIONS

- **Alar LM21.** Revised individual data sheet for Aluminium Casting Alloy LM21. Alar Ltd., 3 Albemarle Street, London, W.1. Free.

This leaflet takes the place of the previous issue known as ALAR 21 since the latter is now incorporated in B.S. 1490. It lists the Chemical Composition, Mechanical Properties, Strength at Elevated Temperature, Physical Properties, Machinability, Corrosion Resistance, Anodising, Casting Characteristics, Heat Treatment and a concluding note on application and general information. References are given to alternative alloys having similar or better qualities for certain uses to save the design engineer from having to make extensive and time absorbing comparisons when selecting alloys.

TRADE PUBLICATIONS

- **Gas and the Schools Meals Service.** Gas Council, 1 Grosvenor Place, London, S.W.1.

This is a useful guide to the equipment required in kitchens generally but are specifically related to the provision of midday meals, as given in M.o.E's Building Bulletin No. 11.

Each item of equipment except refrigerators is described and recommendations are made as to location in relation to other equipment or rooms. Approximate dimensions are given.

The sequence of planning is given, e.g., 1. Entrance to storage centres (dry store, vegetable store or cold room), 2. From storage centres to food preparation, 3. From preparation to cooking, 4. From cooking to hot cupboard for service, 5. From hot cupboard to service counter and dining room, 6. From dining room to wash-up and 7. From wash-up to refuse and swill bins. This logical sequence is not always understood by those new to kitchen planning and cannot always be appreciated when studying kitchen layouts of which a number are illustrated, to cater for 150, 350, 500 and 1,500. Other plans show an arrangement for a boarding school for 200, and a technical college providing both meals and snacks. In each of these care has been taken to see that there is direct access by hatch or door from the dining area to the wash-up, conforming to a very sound principle.

A table is given of the minimum amount of gas-operated equipment which would be needed for normal and for family service, catering for from 75 to 600 persons. Sinks, benches, counter space, etc., are not given but the plans give useful clues.

- **Blacknell Design Sheets.** H. & H. Blacknell Ltd., Farnborough, Hants.

Prefabricated timber framed buildings are shown in this set of twelve sheets covering sports pavilions, village halls, offices, canteens, etc. The prefabricated panels are about 8ft to 10ft long and pre-drilled for fixing to base and to adjacent panels. Externally the cladding is either composed of rebated weatherboard or t. & g. boards. Windows and doors are provided in the panel units as required and no materials are needed for erection and completion beyond those supplied by the makers, including fixing bolts, roofing material, glass, gutters and down pipes, but sanitary fittings, etc., are not available.

The designs shown range from the mundane to the acceptable even if none shows much architectural merit. At least one appreciates that the larger buildings illustrated have good, simple lines and windows of inoffensive shapes which might be repeated in the smaller buildings.

Western Red Cedar is used for some of the framing and insulation to walls and roof can be provided at an extra charge in $\frac{1}{2}$ in insulation board. Alternative roofing materials are available. Trusses of various types are offered according to the spans, most of them knee-braced but plywood cased portal frames are also used.

The designs in this series are in the main only indicative of the range of uses to which the various constructions can be put. Full technical services are available to assist in preparing modifications of any of the types shown to suit circumstances.

Also offered is the "Goliath" range of prefabricated timber buildings, having roof spans from 20ft to 35ft, and lengths in multiples of 5ft. These have double-rafter-and-collar trusses and prefabricated wood roof panels as for the smaller buildings. Alternatively, steel trusses are available. Roof covering is 2-ply felt with alternatives of mineralized felt or tiles. Windows, doors, bolts, ironmongery, wall linings of insulation board, hardboard or plasterboard, glass, gutters, etc., are all included in the specification. Cladding to walls can be either rebated weatherboard with t.e.g. boards to gables, corrugated asbestos or corrugated steel.

The use of prefabricated panels in the construction of these buildings, each to a standard width, enables changes to be made in their arrangement at any time by virtue of the bolted connections while dismantling and re-erection on another site is a practical and economic proposition should the need arise.

- **Caught Red-handed!** The Pyrene Co. Ltd., 9 Grosvenor Gardens, London, S.W.1. Free.

This title introduces a "rate-of-rise" fire detecting system. Abnormal rises in temperature may operate any of a group of sixteen fire detector heads linked with a control unit. This unit has a signal lamp showing normal operating conditions and fire and fault warning signals. The warning system can be transmitted to a fire report centre or to the public fire brigade through a G.P.O. line. This last service is of particular value after the premises have been vacated by staff at the end of the working day. The fault-warning signal is by lamp and buzzer, operating when a fault occurs in the electric wiring, telephone lines or in the main supply. A red lamp and bell give the fire warning. A periodic maintenance service contract is available covering the whole of the installations.

● **Cables by Aerialite Ltd.** Aerialite Ltd., Castle Works, Stalybridge, Cheshire. Free.

The full range of this company's products is listed, described and illustrated in this book and consequently covers Rubber and Thermoplastic cables and flexibles. These are suitable for domestic and industrial electrical installations, mining, farms, street lighting, cars, TV, radio and electronic applications. It is noted that where applicable cables and flexibles are to British Standards but other non-conforming but equally reliable goods are also marketed. Research work continues so as to improve the techniques involved with particularly marked results in the Aeraxial range of co-axial cables.

● **Progress Sheet H.** Frederick Thomas & Co. Ltd., Everton Buildings, Stanhope Street, London, N.W.1.

Glassware for electric lighting for shop, display and home use is illustrated in eight patterns, all in Triplex Opal. Suitable rod pendants are also offered in satin brass with matt white ceiling caps. The glass is finished with a satin velvet texture on the outer surface in preference to a high gloss.



The shapes offered conform with present-day modes based on bottles and barrels, all in small scale, the largest being 15½in high by 5½in diameter. The shades are each designed to take tungsten bulbs of stated wattage which run from 60 watts to 150 watts, larger shades for more powerful bulbs can be made. One shade only has decorative treatment in the form of a vertically striped band either etched or fired black.

The shades can be grouped effectively in multi-light suspensions. Six are illustrated having from two to eight shades in each. The suspension frames are in rod, finished matt black with matt white ceiling cup.

● **Shipston Construction.** Maycrete Ltd., Parliament Mansions, Abbey Orchard Street, Westminster, S.W.1. Free.

This technique has been developed for prefabricated buildings of single storey height—principally dwellings.

One arrangement of a Shipston office building.



The framework is extruded aluminium alloy which in the house component is grooved to receive the wall cladding and lining. The module is 36in with provision for a half-module.

All parts are standardised and, for overseas work, designed for erection by local semi-skilled labour. Aluminium alloy soleplates are rag or gun-bolted to the concrete slab and to these are fixed the uprights which are made rigid with brackets and in addition have wind-bracing within the wall thickness when required. Posts occur at corners, partition junctions, window and door openings. The roof framing is normally supported on wood joists at 3ft centres, which carry the aluminium rafter framework which in turn carries the trough-section aluminium alloy sheets at 22½ degrees. Ceilings are hard-board, cut to size for fixing to wood joists and noggings.

Internal partitions are also framed up on aluminium with additional framing to receive the hardboard at 18in centres.

Thermal insulation is provided by 1in glass wool blanket, the "U" value being about 0.18. When required this can be improved to 0.10 without alteration to construction.

The buildings illustrated by photographs are all houses in hot climates and do not indicate the extent of glare, if any, from the cladding of aluminium. The designs are quite pleasant and the horizontally ribbed treatment of the external sheets gives interest to the cladding.

Provision is made for fly screens, ventilated roofs, etc., and all materials needed for erection are included in the shipment, including timber impregnated against termites when necessary. Equipment included are sanitary fittings, cisterns, pipework, electrical harness, either solid fuel water boiler or immersion heater in cylinder. Kitchen equipment is of a good standard but refrigerator, cooker and washing machine or clothes boiler are optional extras.

A number of sketches of bungalows is included showing on plan various permutations but none is of the "open floor" type which might be more suitable to hot countries. The adaptability of the system is amply demonstrated in the designs for Admiralty housing which are quite extraordinarily inept both as to plan and elevation, creating problems in any form of construction which presumably Shipston have managed to overcome.

Larger buildings such as schools, barracks and small industrial buildings can also be provided in somewhat similar construction.

● **Yale Locks for Master Keying.** Yale & Towne Ltd., Willenhall, Staffs.

A comprehensive brochure has been prepared of this firm's cylinder locks ranging from small padlocks to long mortice locks, all designed for master-keying. The range appears to allow for every requirement in a building, so much wider than one associates with the customary night latch. The variations in types offered are briefly described, such as dead locking, double throw and inside-and-outside key action, to suit various forms and degrees of security which require study to understand their best use and conversely an understanding of the clients' security needs in detail to decide which of the wide range fits precisely the requirements.

As mortice locks, the cylinder system is adapted to operate with a normal case and is available with a double cylinder to work by key from inside and out. Hook and sash locks are also available in the cylinder principle and capable of being mastered.

Information Digest (continued)

● Hursel Heat. Hursel Ltd., 229 Regent Street, London, W.1.

Two folders have been issued illustrating the range of oil-filled electrically heated radiators, towel rails, etc. One folder gives the basis for estimating the wattage required for room sizes, also taking into account the exposure factor of the walls and ceilings. All are heat controlled, either by fixed cut-out or by built-in or wall thermostats. The radiators are available either as fixtures permanently wired up or movable on castors or feet with flexible connections to socket points.

The other folder gives retail prices, type numbers, dimensions, heating surface and approximate weights. Choice of colour is available on some models. All models are for AC but arrangements for DC can be made on some of the types.


● Single Storey Industrial Buildings. Cement & Concrete Association (in conjunction with the Joint Committee on Structural Concrete), 52 Grosvenor Gardens, London, S.W.1. Telephone : Sloane 5255.

A representative selection has been made of recent factory construction employing concrete in one form or another to give a very interesting review of structural design in this medium.

The booklet is divided into sections headed Engineering, Factories for Letting, Pottery, Electrical, Rubber, etc., which, ignoring the confused use of nouns and adjectives, remains unenlightening when a much better division would have been. Shell (part pre-stressed), Shell, Shell North Light, Portal, Post & Truss, etc., for shell roofs are illustrated which roof factories for letting, electrical work, and paper. Moreover, the editorial makes the point that concrete-framed factories having large spans are readily adaptable to many kinds of manufacturing processes.

Ignoring, then, the artificial division adopted, it appears that new ideas are always cropping up, as in the I.C.I. factory at Middlesbrough where the valley beams of the vaults are pre-stressed in one area but this was not

No. 200. Cast iron surround, by Allied Ironfounders, with wooden outer trim. Shown here with Lowburn fire No. 50.



necessary in another part due to more favourable ratio of chord dimension to column centres. Pre-stressing was also used at the Murphy Assembly Shop (architect, C. W. Hutton, F.R.I.B.A.) but only in the ties which tie the edges of the "wings" formed by the two sections of the vaults rising on either side of the valley beams. The travelling framework designed by the contractors (John Laing & Son Ltd.) was also a feature of this contract. Barrel vaults are also used on factories for letting at Crawley New Town, cheapness being a factor in deciding on this type of construction which is an unexpected merit. Fixings for lifting tackle and other overhead equipment have been provided in all parts for the benefit of tenants occupying parts only of the factory structure.

Another form of shell construction was used on a factory for Bowater at Sittingbourne (Farmer & Dark, architects, C. V. Blumfield, B.Sc., Consulting Engineer) in which barrel-shaped frames formed of steel tubes and expanded metal were prefabricated and lifted by crane on to the T.C. supporting beams. Twelve vaults composed of steel tube and mesh were placed in position in three weeks and the *in situ* concrete topping added, the whole of the roof, 450ft by 60ft being completed in five weeks. The underside of the expanded metal is rendered.

A very fine effect is obtained in a factory at King's Lynn for Fropax (H. G. Cousins, B.Sc., for Chisarc and Shell "D" Ltd.) where the seven barrels have chords of 28ft and span 112ft. The valley beams and shells are cambered about 4ft.

Four examples of North Light barrels are shown which differ in detail only.

Pre-stressed work is illustrated in many jobs, largely post and beam types and many have pre-cast posts, cranked beams and purlins with a number of interesting features. A factory at Pontyclun for the South Wales Concrete Pipe Co. Ltd., has pre-cast normal r.c. columns 18ft 2in clear height and pre-stressed concrete equi-pitch trusses over of normal triangulated panels.

Thermal insulation has been described where incorporated. For the Murphy factory lin cork was used on the roof, while 1in and 1in vermiculite screed has also been used. Many factories appear to have no protection against solar gain or winter loss.

The designs are all interesting but few seem to have originality in appearance whatever ingenuity there may be in the structural design. There is still scope for improvement in appearance and in design technique and it is worth noting that Swiss engineers have now evolved an economical method of designing North Light vaults which require no ties or props to the top edge.

● Cast Iron Enamelled Fireplaces. Allied Ironfounders Ltd., 28 Brook Street, London, W.1. Telephone : Grosvenor 8941.

It seems odd that, at a period when through the modernization of out-of-date housing, architects are having some thousands of cast iron fireplaces thrown out, anyone should try to sell cast iron fireplaces to put in their stead. The old fine-cast raised basket grates and backs were excellent pieces of work and gave out good heat though perhaps at rather a high rate of combustion. Other old cast iron grates were mean and ugly and unendurable.

The new fireplaces are offered finished in "attractive shades of vitreous enamel" but no colours are quoted although some ordering details are given. Presumably the buyer has a choice? The quality of design offered is mixed. The No. 200 suite has a simple reeded front with wood (kind not stated) trim around. The No. 195 is

NAUTILUS FLUE BLOCKS TYPICAL INSTALLATIONS: MULTI STOREY ELEVATION

SPECIFICALLY DESIGNED FOR GAS FIRES

NAUTILUS
GAS FIRE FLUE
S.3.

AND TO ENSURE ADEQUATE VENTILATION

NAUTILUS PRECAST CONCRETE FLUE BLOCKS

made by **MARLEY**


Registered user of Nautilus Trade Marks Nos. 424, 327 & 602, 684.

SEND FOR INFORMATION TO:—THE MARLEY TILE COMPANY LIMITED • SEVENOAKS • KENT • SEVENOAKS SS255

Free House!



It wasn't supposed to be an invitation. The trouble is so many old locks do no more than just keep the door closed (and sometimes not even that) whilst real security measures are non-existent. The safest course if you value your property is to re-equip all important doors inside and out with the world's most reliable locks — YALE. There are YALE locks and padlocks to meet every security risk. Here is an example:



M.555 LEVER MORTICE DEADLOCK

The latest lock for keeping out the uninvited 'guest' from lock-up premises. Designed to meet insurance requirements, it is a 5-lever deadlock operable by key from both sides. Differs are obtainable on levers only and not by use of wards, making it extremely difficult to pick. Its steel reinforced deadbolt and 10" steel striking plate make it almost impossible to force. Available ex stock; literature on request.

Where there's a door there's a need for



Information Digest (continued)

similar but without wood trim. The former, with back boiler, costs about £21 and the latter about £17, both including enamelled cast iron hearths and curbs. A convector pattern is offered as Type 190C with hearth, curb and back boiler at about £34.

Other designs are offered but scarcely achieve the quite modest standard of appearance of the three quoted.

● **Belling Electric Fires and Cookers.** Belling & Co. Ltd., Bridge Works, Southbury Road, Enfield, Middx.

Two catalogues are now available, one in booklet form and one as a double-sided folder for wall display. Both have full colour illustrations of the larger items of equipment and show electric fires, cookers, convectors, drying cabinets, bed warmers, towel airers and boiling rings and plates.

Many of the fires are old acquaintances, some based on even older fashions to appeal to "period" enthusiasts while some of the fires and most of the convectors are well designed with lines to fit in with "contemporary" furniture. The "Overnite" heater is now introduced where low tariff night supplies are available. Various commercial and industrial warm air heaters from 250 watts are also offered. The range of cookers includes the

Belling Plus Auto-timer which has clockwork switches for automatic on-and-off switching combined with thermostatic control. A "reminder-timer" gives audible warning when cooking time has expired.

● **Escape from Fire.** Fire Protection Bulletin, Fire Offices Committee, Fire Protection Association, 15 Queen Street, London, E.C.4. Free.

This Bulletin deals with cut-off doors to staircases, minimum widths of doorways and stairs and number of steps in a flight. It therefore covers ground which ought to be fully understood by architects and builders but possibly those not normally concerned with offices and warehouses may not be conversant with good practice. The Bulletin mentions but does not stress that panic is in some ways worse than the fire itself, hence the need to keep smoke out of stairways and escape passages by having self-closing cut-off doors. No mention is made, either, of the need to ensure that doors when opened do not reduce the width of the escape passage or stair.

Advice is given as to the authorities to be approached for guidance on escape matters, to which might be added the Fire Protection Officer of the county where such an office has been created.

Timber Notes

MOST of the changes in the timber market lately have been due to the activities of the Russian sellers. In softwood, they have offered 60,000 standards, of which 50,000 standards are redwood and 10,000 standards whitewood, for sale from those areas remaining open to shipping at prices which generally show a reduction on those quoted in Russian softwood sales this year.

The price for 7in unsorted redwood d.b. stays at the figure of £94 a standard c.i.f., but in some of the smaller sizes and in the boards, both in redwood and whitewood, there have been reductions. Most of them are 30s and £2 a standard lower than the July quotations, but some are larger, the unsorted redwood battens of 2in by 5 in and under being priced at £9 lower.

Such a price schedule would normally have led to a lot of buying by the importers, but in fact only about a fifth of the quantity offered was taken up in the stipulated time, though there has been some later selling. The reason for this apparent indifference among the importers towards this bargain sale was the belief that even better prices might be quoted on the market in the next few weeks. The Russians tried to safeguard buyers of 250 standards and upwards by offering a fall clause, which meant that, should there be any lowering of the Russian prices by

the time shipment was made, then the lower prices would apply.

There is believed to be a good quantity of softwood still to be sold by Finland and Sweden, and these countries might try to force the slow pace of sales by dropping quotations considerably. Most of the importers have already bought to meet their estimated requirements up to next May, so they can afford to wait for bargains.

In the plywood market the Russians have been more drastic in their price changes. Plywood has dropped in value this year more than a quarter, making this one of the most depressed of the commodity markets. The Russians placed some 40,000 cu. metres of birch plywood on the market following the offer of the Government-held Russian birch plywood, and both sales proved highly successful. The Government stocks were sold, and the Russians have been able to dispose of most of their plywood.

Sharp reductions were announced by the Russians. Taking the list price of last year as the basis, the new prices showed a fall of 32 per cent where the purchase was 5,500 cu. metres or over, and there were smaller reductions down to 25 per cent for 250 cu. metres. Some importers combined in their purchasing to gain full advantage of the discount rate.

Prices asked by the Government in the plywood sale were on the low side, and only a small quantity of Canadian Douglas fir plywood remains unsold.

This will probably go mainly to the building trade. The Government hardwood stock disposal was also quite successful, and there now remains a relatively small quantity of American red oak still to be sold. The Government softwood sale moves slowly, however, for there has been no change in the price ideas of the Board of Trade officials on the value of this wood.

As is customary at this time of the year, stocks in all sections of the timber trade are good. If the present rate of consumption can be taken as a guide, then the stocks will be adequate for many months to come, irrespective of what happens on the international market.



Laminated ceiling in Earley Generating Station.

Public Works and Municipal Services Congress

Thirty-four Papers on a wide variety of subjects will be presented during the 29 sessions of the Public Works and Municipal Services Congress to be held at Olympia, London, from November 12 to 16. The Exhibition, run in conjunction with the Congress, will continue until Saturday, November 17. After the Congress has been opened by its President, the Minister of Housing and Local Government, the first session will be held. All papers will be taken as read and the authors will briefly introduce their papers and speak at greater length in reply to the discussion.

PROGRAMME

Monday, November 12, 2.30 p.m. Official opening of the Congress and Exhibition by the Rt. Hon. Duncan Sandys, M.P., Minister of Housing and Local Government, President of the Congress Council. 3.0 p.m., "Essentials for a Modern Engineer," by Mr. A. S. Turner, M.I.Mun.E., A.M.I.C.E., Deputy County Surveyor, Somerset. "Problems in Underground Pipe Design and Pipe Laying," by Mr. N. W. B. Clarke, of the B.R.S. "The Control and Treatment of Industrial Wastes," by Mr. W. Fillingham Brown, B.Sc., M.I.C.E., F.I.P.H.E.

Tuesday, November 13, 10.30 a.m. "A County Highway Repair Depot and the Organization and Maintenance of Plant," by Mr. J. H. H. Wilkes, B.Sc., M.I.C.E., M.I.Mun.E., County Surveyor of Somerset, and Mr. F. B. Kelly, A.M.I.C.E., Chief Plant Superintendent, Somerset C.C. Central Repair Depot. "The Reconstruction of Cities," by Mr. Arthur Ling, B.A., A.R.I.B.A., A.M.T.P.I., City Architect and Planning Officer, Coventry. "Gas in the Production and Maintenance of Public Service Vehicles," by Mr. T. H. Pardoe, M.Inst.Gas E.,

M.Inst.F., Area Industrial Engineer, South Western Gas Board. "Heat Services by Coke in Municipal and School Buildings," by Mr. C. A. Deas, M.Inst.F., M.Inst.Gas E., Coke Officer, Eastern Gas Board, 2.30 p.m. "Modern Trends and Developments in Road Maintenance Technique," by Mr. J. R. Musgrave, A.M.I.C.E., A.M.I.Mun.E., Senior Assistant County Surveyor of Staffordshire, and Mr. J. V. Leigh, M.B.E., B.Sc., A.M.I.C.E., A.M.I.Mun.E., Assistant County Surveyor of Staffordshire. "Post-War Flat Development in Europe," by Professor R. A. Jensen, B.Arch., F.R.I.B.A., A.M.T.P.I. "Street Lighting Economics," by Mr. N. Axford, B.Sc., M.I.E.E., Manager, Plymouth District, South Western Electricity Board.

Wednesday, November 14, 10.30 a.m. "The Influence of Road Layout on Speeds and Accidents in Rural Areas," by Mr. G. Charlesworth, B.Sc., Ph.D., F.Inst.P., and Mr. T. M. Coburn, B.Sc. "Accident Studies Before and After Road Changes," by Mr. F. Garwood, M.A., Ph.D., F.S.S., and Mr. J. C. Tanner, M.A., F.S.S. "Accident Reports and Skidding Accident Sites," by Mr. C. G. Giles, B.Sc., A.Inst.P., and Miss B. E. Sabey, B.Sc. "Hygiene and Sanitation in the Fish Industry," by Mr. R. Spencer, Humber Laboratory, Food Investigation Organization of D.S.I.R., Hull. "Problems of Horticulture in a Seaside Resort," by Mr. E. W. Studley, A.H., R.H.S., F.Inst.P.A., Director of Parks, City of Portsmouth. 2.30 p.m. "The Importance of Control in Road Construction," by Mr. A. R. Lee, B.Sc., Ph.D., F.Inst.P. "Control in the Manufacture and Laying of Bituminous Materials," by Mr. H. G. Barnes, B.Sc., A.M.I.C.E. "Control in Mixing and Placing Concrete," by Mr. R. H. H. Kirkham, B.Sc., Ph.D.,

A.M.I.C.E. "Non-Destructive Tests of Roads and Structures," by Mr. R. Jones, B.Sc., Ph.D. "Development Plans: Their Form and Effects," by Mr. J. F. Q. Switzer, M.A., A.R.I.C.S., Department of Estate Management, University of Cambridge. "Some Aspects of Park Administration in an Industrial Area," by Mr. T. L. Ashton, N.D.H., D.Inst.P.A., Superintendent of Parks, Cemeteries and Allotments, Borough of Keighley. "The Small-Holder: His Contribution to Britain's Food Problem," by Mr. J. W. Cassels, O.B.E., B.Sc., Director of Agriculture, County of Durham.

Thursday, November 15, 10.30 a.m. "Development of New Towns," by Lt.-Col. A. Borlase, T.D., M.I.C.E., M.I.Mun.E., Chief Engineer, Cwmbran (Mon.) Development Corporation. Session under the auspices of The British Waterworks Association—Debate on Drought. "The Repair and Improvement of Houses," by Mr. J. Marriott, M.I.Mun.E., F.S.I.A., Chief Health Inspector, Engineer and Surveyor, Wetherby R.D.C. 2.30 p.m. "Economic Efficiency of Transportation by Road and by Railway," twin papers by Mr. W. H. B. Cotton, M.I.Mun.E., A.M.I.C.E., County Surveyor of Durham, and Mr. C. E. R. Sherrington, O.B.E., M.C. M.A.(Cantab.), M.Inst.T., Director of the Research Information Division, British Transport Commission. "Radio-Activity and the Water Industry," by Mr. Arthur W. Kenny, M.A., B.Sc., F.R.I.C., Radio-Chemical Inspector, Ministry of Housing and Local Government. "Environmental Sanitation: Past, Present and Future," by Mr. G. W. Herrick, D.P.A., F.S.I.A., Chief Sanitary Inspector, Fulham M.B.C.

Friday, November 16, 10.30 a.m. "Re-Location of Employment," by Mr. L. W. Lane, A.M.T.P.I., A.R.I.C.S. "Factors Affecting the Concentration of Dissolved Oxygen in the Thames Estuary," by Mr. A. L. H. Gameson, M.A., and Mr. W. S. Preddy, M.Sc., of the Water Pollution Research Laboratory, D.S.I.R. "Mechanised Composting," by Mr. J. C. Wylie, B.Sc., M.I.C.E., A.M.Inst.P.C. 2.30 p.m. "Expansion of Small Towns, Planned and Unplanned," by Mr. D. W. Riley, M.T.P.I., M.I.Mun.E., County Planning and Development Officer, Staffordshire. "The Settlement of Sewage," by Mr. T. Stones, M.Sc., Ph.D., F.R.I.C., M.Inst.S.P., Sewage Works Manager and Chemist, Salford C.B. "Public Cleansing—Night and Day," by Mr. T. B. Finnie, M.Inst.P.C., Deputy Director of Cleansing, City of Glasgow. "Quarterway Stage in a County Road Plan," by Mr. J. Drake, B.Sc., M.I.C.E., M.I.Mun.E., F.Inst.H.E., County Surveyor of Lancashire.

MOVITEX
NOTICE BOARDS
COMPLETE WITH
INTERCHANGEABLE
CHARACTERS

| |
|-----------|
| 15" X 12" |
| 23" X 15" |
| 30" X 23" |
| 46" X 23" |

EASY TO OPERATE.
IDEAL FOR STAFF NOTICES
MENUS, ETC

The Movitex notice board is distributed by Adapta-Charts Ltd. It is easily interchangeable and can be used for permanent notices or those that must be frequently altered. The metal framed board is available in five different sizes ranging from 12in by 7½in to 23in by 46in. The board itself is of ½in black Bakelite sheeting backed with ½in thick tempered press wood. Three-dimensional plastic characters, in red or white, fit into perforations in the surface.

There's something new in the pipe line



IT'S THE UNION PITCH FIBRE PIPE, the biggest news in piping since hollowed-out tree trunks became unfashionable. Light instead of heavy, resilient instead of rigid, tough instead of brittle, Union Pitch Fibre Pipes will do anything that conventional drain-pipes will do—and do it at much smaller cost. There are many reasons for their economy of working; the chief among them are:

1. Union Pitch Fibre Pipes are supplied in 8 ft. lengths with accurately machined ends to provide a simple driven joint.
2. They can be laid without any concrete bedding or haunching, and can be cut and machined on site where necessary. Moreover, they are so light that one man can easily carry 32 ft. of piping.


If you'd like to know more we'll gladly send technical literature. Union Fibre Pipes (Great Britain) Ltd., Tolpits, Watford, Herts. Telephone: Gadebrook 4551.

UNION PITCH FIBRE PIPES

save time and money




A MEMBER OF THE U.A.M. GROUP OF COMPANIES



NSE

CLOTHES LOCKERS



Factory Regulations call for the provision of suitable lockers for all employees and the N.S.E. range can fulfil these requirements.

Lockers are produced in banks to suit individual layouts and are valuable either as full length lockers or with two or four individual compartments in height. Full details on application.

NORWOOD STEEL EQUIPMENT LTD

MAKERS OF STEEL OFFICE & WORKS EQUIPMENT

149 BOROUGH HIGH ST., LONDON, S.E.1. HOP 5033 P.B.X.

NORTHERN OFFICE: 357 OXFORD ROAD, MANCHESTER, 13. ARDwick 1701

WESTERN OFFICE: 3-5 SUSSEX PLACE, ASHLEY ROAD, BRISTOL, 2. BRISTOL 57406

Industrial Notes

● An interesting feature of the Daily Mail Ideal Home Exhibition at Olympia in March, 1957, will be a Canadian timber frame house. The house will incorporate the latest advances in modern living and is being designed by Architects Wells and Hickman. Builders and furnishers of the house will be Heal & Sons Ltd., Tottenham Court Road, London. The demonstration house is being sponsored by the British Columbia Lumber Manufacturers Association in co-operation with the Canadian Government. It will be a two storey frame structure with brick facing along the sides of the building and Cedar weatherboarding at the front and back. Various applications of Canadian timber, both structurally and decoratively, will be shown. Mr. G. C. Edgett, Timber Development Director of the B.C.L.M.A., said recently: "We have given the Architects a rather interesting challenge. We have asked them to produce an attractive design for a three bedroom house, costing no more than £3,500 which will have a spacious open plan, ample storage and cupboard space plus oil-fired controlled heating. We believe that these are features which the prospective British home-owner soon will be demanding. Our aim is to show how these amenities can be provided in a frame house without paying more than the cost of a traditional house without such attractions."

● We regret to announce the death of Mr. W. J. Skevington, Chairman of Joseph Freeman Sons & Co. Ltd., which occurred on Wednesday, September 19. Mr. Skevington, who was associated with the Building Industry for over 60 years, was

responsible for the world-wide development and popularization of "Cementone".

● The Contractors' Plant Association has published a Handbook, which should be of great value to all concerned with contractors' plant. It contains in one volume a great deal of useful information relating to the hiring and operation of contractors' plant. In addition to the names and addresses of the members of the Association (both alphabetically and under counties), it includes the schedule of recommended rates of hire, the general terms and conditions for the hiring of plant, the Working Rule Agreement of the Civil Engineering Construction Conciliation Board and the agreements covering the Holidays with Pay schemes. There is also a section on legislation affecting contractors' plant and commercial road vehicles, comprising relative extracts from the Factory Act, the Building Regulations, the Road Traffic Act and giving comprehensive details of capacity, weights and measurements of a number of items of plant and the names of manufacturers and importers in classified lists. The price of the Handbook is 12s 6d including postage, and copies can be obtained from the Contractors' Plant Association at Hanover House, 73/78 High Holborn, London, W.C.1.

● Rubber Improvement Ltd. announce a trading profit for the year ended May 31, 1956, of £914,000 approximately, compared with £512,000 for the previous year. The final dividend declared on all the Ordinary Issued Share Capital of the Company is 40 per cent.

● The Ketton Portland Cement Co. Ltd. made a profit for the year ended June 30, 1956, of £149,178, after deduction of tax. The final dividend on the Ordinary Shares is 15 per cent, less tax, together with a bonus of 5 per cent less tax.

● Brick Investments Ltd. announce a profit for the past year of £15,799, after deduction of income tax. This compares with £13,015 declared for the previous year. The final dividend payable is 15 per cent less income tax on the Ordinary Shares, making a total distribution of 20 per cent for the year.

● Horseley Bridge & Thomas Piggott Ltd. announce a Group profit, after deducting taxation, of £126,143 for the year ended March 31, 1956. They announce a final dividend of 15 per cent on the Ordinary Shares.

● International Paints (Holdings) Ltd. celebrated the Company's 75th anniversary with a dinner held at the Savoy Hotel. Mr. C. R. Petrie, the Chairman and Managing Director, reviewed the growth of the Company during the course of his speech.

● The wedding took place on Friday, September 21, at Caxton Hall, followed by a church service at St. Simon Zelotes, of Mr. Francis Taylor, of Aldford Street, W.1, chairman and founder of Taylor Woodrow Ltd., building and civil engineering contractors, and Miss Christine Enid Hughes, of Reeves Mews, W.1, a director of Taylor Woodrow Homes Ltd., and Southern Province Farms Ltd.

● Three new Directors, Mr. G. V. Cumbers, Mr. John A. Findlay and Mr. G. L. Gomm have been appointed to the board of Unity Structures Ltd.


● The Appliance Division of The English Electric Company Ltd. announce the appointment of Mr. L. C. Eaton to be sales representative in the South Western territory of the L.E.B. area. He will work from Queen's House, Kingsway, under Area Manager Mr. A. W. H. Bradstreet.

● F. Hills & Sons Ltd., of Stockton-on-Tees, manufacturers of flush and panel doors, windows and "Duramel" plastic faced plywood (previously known as "Durette") have appointed Mr. Ramsay Howarth as their representative in Scotland and Northern Ireland. Mr. Howarth's private address is: 90 Old Dalnottar Road, Old Kilpatrick, By Glasgow. Telephone: Bowling 1141.


● The new address of the Battelle Institute Limited is 24 Ryder Street, St. James's, London, S.W.1. Telephone No. Trafalgar 1621.



A new passenger lift, capable of accommodating 55 people, which has been installed at Queensway underground station. Lift contractors were Wadsworth & Sons Ltd., under the direction of the Lifts and Escalators Division of L.T.E. Frederick Sage & Co. Ltd., the sub-contractors for the lift cars, installed Warerite plastic panelling in two shades of green.



NEW PRODUCTS




Two new gas fires have been added to the range of Wm. Sugg & Co. Ltd. The first of these, the "Sussex", Fig. 1, is a convector radiator with a gas rating of 9000 B.Th.U./Hr. The fire measures 31in high by 16½in wide by 9in deep. The body and surround are made of sheet steel and the louvre grill, base and front frame of aluminium. The second fire, the "Vincent", Fig. 2, is a radiant hearth model with a gas rating of 19000 B.Th.U./hr. Overall measurements are 25in high by 20½in wide by 8½in deep, with 6in projection from fireplace face. Body and surround are of sheet steel and trivet and coves of anodised aluminium. In both fires the outer casings are completely detachable. The "Sussex" is finished in gold and the "Vincent" in bronze and gold stove enamel.

4½in wide and internally the bath measures 5ft 0½in long by 2ft 0½in wide by 15½in deep. Available in several colours.

The 6ft bath, Fig. 4, manufactured by Wemyss Woodhouse Ltd., is constructed from Cellobond polyester resins (made by British Resin Products Ltd.) and glass fibre. The bath is 31in wide and weighs only 45lb. It is in self coloured white; soapy water is recommended by the makers for cleaning after use. It is claimed that the bath itself is never cold to the touch and that as the material is a good heat insulator the bath water keeps hot longer. The same claims are made for the universal sink unit, Fig. 5, which can be easily drilled or cut.

The Atlanta bath, Fig. 3, is the latest to be produced by Bilston Foundries Ltd. It is shallow and flat-bottomed. The panels are 17in to 21½in high with adjustable feet and 15½in without feet. The outside measurements are 5ft 6in long by 2ft



The "Staffa" barge crane by Chamberlain Industries Ltd., is equally suitable for fixed mounting or for mounting on a prime mover to operate as a truck crane although it was originally designed for the well in the bow of a barge. It is hydraulically operated and has a capacity of 10cwt at 30ft radius with lifting speeds up to 150ft per minute derricking speeds from 12/30ft radius in 17 seconds and a slewing speed of 4 r.p.m. The crane has a 30ft Cantilever lattice type jib and the superstructure carries a Ford 4-cylinder diesel engine directly coupled to a Plessey pump with capacity of 24 gallons per minute.

Pluvex roof felt is now available with a coat of ceramic sand in red or green. Manufactured by the Ruberoid Co. Ltd., this felt is supplied in rolls of 12 sq yd measuring 36in wide.


Hyflux-al is a new soldering flux produced by Whiffen and Sons Ltd. It is based on hydrazine and prepared for use in conjunction with solder. It is claimed that the hydrazine compound is a powerful reducing agent which removes the oxide film on aluminium and decomposes and/or volatilizes quickly at 300 deg C without leaving a residue, if soldering is

carried out at the correct temperature.


International Paints Ltd., have brought on to the market a new type of paint finish called Policrome. The Policrome film is multi-coloured, two or more colours being simultaneously applied to the surface in one single spray coat. It is claimed that the multiple colours exist separately within the Policrome finish and upon being sprayed, create an interlacing colour network. The thousands of flecks of colour blend to give an effect of vibrant colour harmony from one can of paint in one application. This finish has been in use for some time in Canada and U.S.A. and the makers state that it may be applied to concrete, plaster, canvas, wood, building boards, lining papers and various metals and plastics. It is manufactured in 17 basic colours and no thinners are required. It may be generally described as a washable semi-flat paint which claims the following properties: dirt and grease do not settle on it, it is hard to scratch or chip, touching-in is not noticeable, improves rather than impairs the sound absorption value of acoustic ceilings, has high resistance to oils and acids and does not emit spray dust or fog when being sprayed. It is quick drying and has a spreading capacity of 20/25 sq yds per gallon.

Dexion Ltd. have increased the range of their slotted angle by the introduction of two new sizes. No. 140 with equal flanges of 1½in by 1½in designed to bolt together with all other Dexion angles. It is smaller than sizes 225 and 300 and is designed for factory, store or office jobs where the strength of the larger members is not needed or for lightly stressed members in bigger structures. No. 112 is a half-sized version of No. 225 and is designed for models, display stands and frames, small laboratory and workshop frameworks, etc. Both the new components are available in steel and aluminium alloy. Five new sizes of 19 s.w.g. stove-enamelled steel shelves are also available in battleship grey finish. All are 36in long with flanges of 1½in and the depths are 12, 18, 24, 30 and 36in.

Permanite Ltd. have introduced Permicolor which is a new coloured roofing felt, claimed to be dust less. It is supplied in green or red finish and in rolls measuring 12yd by 1yd.




4



5

AT THE EARLIEST STAGE

it pays to consider Oil Heating




- * No passages or chutes required for fuel delivery. Oil bunkering pipes are small: they need not interfere with the layout of the building.

- * Instant, automatic and accurate heat control possible, through wide variations to meet fluctuating loads.
- * Outstanding cleanliness in use, high burning efficiency and negligible ash content — resulting in reduced handling costs, storage space and ash disposal.

It pays to say **ESSO FUEL OILS**

For further information write to: ESSO PETROLEUM COMPANY, LIMITED, FUEL OIL DIVISION, 36 QUEEN ANNE'S GATE, LONDON, S.W.1

**"I'm
going
down,"
said the
frogman,
"to look
at our
walls"**



There are more ways of inspecting a wall surface than that of climbing up a ladder. At a place in the Channel Islands, you dive into 12 feet of water. There, on the side of a certain swimming pool, and very much against our wishes,


you will find Pammastic—doing fine. It is not, of course, designed for life underwater.

But this happy misuse provides a dramatic demonstration of a point that deserves publicity—*Pammastic is the plastic emulsion paint that can be used outside a building as well as inside.*

Suitable for most surfaces, it needs no primer or undercoating, and dries in an hour. Its fine matt surface can be washed down and scrubbed clean repeatedly. Further information about the remarkable properties of Pammastic—and its notable complementaries, Pammel (the luxury gloss enamel), Pammelette (the superfine eggshell enamel) and Pammatt (the superfine flat enamel)—is available on request.

BLUNDELL PAINTS

BLUNDELL, SPENCE & CO. LTD., YORK HOUSE, 37 QUEEN SQUARE, LONDON, W.C.1.




FLUORESCENT TUBES

SHOWCASE

ILLUMINATED CEILING

SECTION A-A • 1/4" = 1' 0"



DEEP RED STONITE RENDERING ON EXP METAL


FLUORESCENT TUBES

ILLUMINATED CEILING

ILLUMINATED CEILING BETWEEN FINS


ROOF DECKING

SECTION B-B • 1/4" = 1' 0"




TRACK HANGER

FIXING FOR TRACK HANGER



ELEVATION OF CENTRE CANOPY • 1/8 F.S.



SKETCH SHOWING FIXING OF CEILING



CANOPY DETAIL, CINEMA, BIRMINGHAM
ARCHITECT: H. WERNER ROSENTHAL



READERS' INFORMATION SERVICE

Catalogues and further information relating to Manufacturer's and Specialist's advertisements in this issue will be forwarded if you fill in the names and page numbers on the reply paid postcards below.

THE ARCHITECT & BUILDING NEWS *Readers' Information Service*

Advertiser's name only Page No. Advertiser's name only. Page No.

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Reader's Name and Address.....

Profession or Trade.....

DATE OF ISSUE 11 OCTOBER, 1956

Postage
will be
paid by
Licensee

No Postage
Stamp
necessary if
posted in
Great Britain
or
Northern Ireland

BUSINESS REPLY CARD
Licence No. SE 591

ILIFFE & SONS LTD.,
THE ARCHITECT & BUILDING NEWS
Reader's Information Service,
DORSET HOUSE,
STAMFORD STREET,
LONDON, S.E.1.



READERS' INFORMATION SERVICE

Catalogues and further information relating to Manufacturer's and Specialist's advertisements in this issue will be forwarded if you fill in the names and page numbers on the reply paid postcards below.

Postage
will be
paid by
Licencee

No Postage
Stamp
necessary if
posted in
Great Britain
or
Northern Ireland

BUSINESS REPLY CARD
Licence No. SE 591

ILIFFE & SONS LTD.,
THE ARCHITECT & BUILDING NEWS
Reader's Information Service,
DORSET HOUSE,
STAMFORD STREET,
LONDON, S.E.1.

THE ARCHITECT & BUILDING NEWS Readers' Information Service

Advertiser's name only Page No. Advertiser's name only. Page No.

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Reader's Name and Address.....

Profession or Trade.....

DATE OF ISSUE 11 OCTOBER, 1956

Notes below give basic data of contracts open under locality and authority which are in a bold type. References indicate: (a) type of work (b) address for application. Where no town is stated in the

CONTRACT • NEWS •

OPEN BUILDING

CUMBERLAND C.C. (a) Erection of (1) three permanent classrooms and corridor at Harrington junior school, nr. Workington; and (2) one transportable timber classroom at Bowness-on-Solway school. (b) County Architect, 15 Portland Square, Carlisle. (c) (1) October 31 and (2) October 22.

DEAL B.C. (a) 40 houses in pairs and blocks of four on St. Martin's Road estate. (b) Borough Engineer, Municipal Offices, Queen Street. (c) 2gns. (d) October 19. (e) November 6.

DEVON C.C. (a) Erection of a police house at Coplestone. (b) County Architect, 97 Heavitree Road, Exeter. (c) 2gns, by cheque payable to Council.

DEVON C.C. (a) Erection of classroom, kitchen, stores, etc., at Cullompton primary school. (b) County Architect, 97 Heavitree Road, Exeter. (c) 2gns, by cheque payable to Council.

DURHAM C.C. (a) Adaptations at Stockton Technical College, Oxbridge Avenue. (b) County Architect, South Street. (d) October 17.

EAST KESTIVEN R.C. (a) Two pairs of bungalows at Osbournby. (b) Council's Architect, Council Offices, 14 Northgate, Sleaford. (c) October 27.

EIRE—KERRY. (a) New Church of the Immaculate Conception at Killeen-tierna. (b) Chevalier Patrick J. Sheahan, 47 O'Connell Street, Limerick. (c) £52 10s. (e) October 26.

ESSEX C.C. (a) Kitchen and dining room at Hockley High Road primary school, to cost approx. £8,000. (b) County Architect, County Hall, Chelmsford. (d) October 20.

HASTINGS CORPORATION. (a) (1) Two prefabricated practical rooms and boiler chamber at Hastings secondary school for boys, Priory Road; and (2) two classrooms, cloakrooms and toilets at Red Lake infants' school, Ore. (b) Borough Engineer, 37 Wellington Square. (c) 3gns. (d) October 15. (e) November 26.

KESTIVEN C.C. (a) Two pairs of police houses at Radcliffe Road, Stamford. (b) County Architect, County Offices, Sleaford. (e) October 19.

LANCASHIRE C.C. (a) One pair of police houses at Lancaster Drive, Clayton-le-Moors, nr. Accrington, and one pair at St. Albans Road, Darwen. (b) County Architect, P.O. Box No. 26, County Hall, Preston. (d) October 15, quoting Ref. A/MG.

LEEDS REGIONAL HOSPITAL BOARD. (a) Carrying out alterations to provide dining accommodation at Bootham Park Hospital, York. (b) Board's Architect, Park Parade, Harrogate. (c) 2gns. (d) October 16. (e) November 6.

address it is the same as the locality given in the heading (c) deposit (d) last date of application (e) last date and time for submission of tenders. Full details of contracts marked * are given in the advertisement section.

**THE ROOF
OVER OUR HEADS
IS
YOUR PRESTIGE AND OURS**

When you specify our built-up roofing you specify a century of experience in the best products obtainable. Thus our prestige becomes your prestige and vice versa.

ENGERT & ROLFE LTD
LONDON E 14 (EAST 1441)
and THE QUAY EXETER
(EXETER 3595)



CHAIRS
OF SUPERIOR QUALITY

CHEAP Chairs for Canteens, British Restaurants, Halls, etc. Personal attention given to all Orders.

Mealing Bros. Ltd.

Avenue Chair Works,
West End Road,
High Wycombe.



Telephone: Wycombe 499. Catalogue on application

Specify
CERRUX
DECORATIVE PAINTS
CELLON LTD., KINGSTON-ON-THAMES

**BOSTWICK
METALWORK**

OF EVERY DESCRIPTION &
OUTSTANDING EXCELLENCE

BOSTWICK GATE & SHUTTER Co. Ltd.

Original Patentees of the Collapsible Gate.
HYTHE ROAD, WILLESDEN, N.W.10
Telephone: LADBroke 3661

HIGH QUALITY WHITE FACING BRICKS

(S.P.W. BRAND)

As supplied to the WAR OFFICE, H.M. MINISTRY OF WORKS, AIR MINISTRY. Etc.

Sample and Brochure
sent on request

**M. MCCARTHY
& SONS, LTD.**
BULWELL — NOTTINGHAM

The
Stainless Steel Sink
Co. Ltd.
Manufacturers of

PLAND
SINKS

Head Office:
Ring Road, Lower Wortley, Leeds, 12
London Office:
14 Great Peter Street, S.W.1.

London's Finest new & secondhand Value
ARCHITECTS' PLAN CHESTS

Steel & Wood Office Furniture
Filing Cabinets
Safes—Chairs—etc.

M. MARGOLIS

178-180 BURY ROAD, LONDON—E.11. Phone: FUL 7322

**SZERELMEY
SILICONE**

WATERPROOFS
AND PRESERVES
ALL MASONRY

ASK FOR
**SZERELMEY STONE LIQUID
NO. 103**

SZERELMEY LTD.
275 Rotherhithe New Rd., London, S.E.16

LEATHERHEAD U.C. (a) 16 dwellings at Great Bookham. (b) Council's Engineer, Red House. (c) 2gns. (e) October 26.

LEICESTER C.C. (a) Alterations and additions at Ashby Ivanhoe secondary school. (b) County Architect, 123 London Road. (e) November 3.

LIVERPOOL C.C. (a) (1) 13 houses, Saunby Street, Liverpool, 19; (2) 5 houses, Mab Lane, Liverpool, 12; and (3) 16 houses, Greaves Street, Liverpool, 8. (b) City Architect, Blackburn Chambers, Dale Street, Kingsway, Liverpool, 2. (c) 2gns each contract. (e) October 18.

LONDON—CHINGFORD B.C. (a) (1) 28 houses at Kimberley Way, Chingford; and (2) 24 houses at The Bramblings, Chingford. (b) Borough Engineer, Town Hall, Chingford, E.4. (c) 2gns each contract. (e) (1) October 31; (2) November 28.

LONDON—WALTHAMSTOW B.C. (a) Conversion of No. 880 Forest Road, Walthamstow, E.17, into seven bed sitting-room flats. (b) Borough Architect, Town Hall. (c) 2gns. (e) October 19.

LOWESTOFT B.C. (a) Erection of (Group A) 32 houses, (Group B) 40 houses, (Group C) 24 houses, and (Group D) 40 houses at Beeches estate. (b) Borough Engineer, 49 High Street, Lowestoft. (c) 2gns. (e) October 26.

LUTON B.C. (a) (1) Caretaker's house at the St. Joseph's Roman Catholic primary school; and (2) proposed alterations to provide new classroom accommodation at Leagrave primary junior school. (b) Borough Architect, Town Hall. (c) 2gns each contract. (e) November 6.

LUTON B.C. (a) Erection of proposed staff room and lavatory accommodation at Surrey Street C.P. infants' school. (b) Borough Architect, Town Hall. (c) 2gns. (e) October 22.

MANCHESTER CORPORATION. (a) Carrying out alterations and extensions to Abbey Hey primary school. (b) City Architect, P.O. Box 488, Town Hall. (e) October 24.

MIDDLESEX. (a) 72 flats with roads, paths, garages at Eastcote, Middlesex. (b) Hugh C. Duncan, Esq., 9 Hertford Street, Park Lane, London, W.1. (c) 5gns from contractors selected to tender.

MITFORD AND LAUNDITCH R.C. (a) (1) Erection of one pair of houses and two pairs of bungalows, together with site preparation and external services, at Beeston; (2) alterations to the existing sewage disposal plant, consisting of construction of approx. 800ft of irrigation drain, at Billingham; and (3) construction of a sewage disposal plant to serve 53 dwellings, main drainage and roadworks to the new housing site, at Shipdham. (b) Mr. Harold Marsh, 4A Market Place, Dereham, Norfolk. (c) 2gns. (e) October 27.

NEW FOREST R.C. (a) Erection of (1) 26 pairs, one block of four and one block of six houses, forming Contract No. 6, Site No. 53, Langdown Croft, Hythe; (2) three blocks of six houses forming Contract No. 5, Site No. 56, Salisbury Road, Totton; and

(3) two pairs of bungalows forming Contract No. 6, Site No. 56, Salisbury Road, Totton. (b) Council's Engineer, Appletree Court, Lyndhurst. (c) 2gns. (e) October 22.

N. IRELAND—DOWN EDUCATION COMMITTEE. (a) Erection of a new primary school in prefabricated timber units at Knockbreda. (b) Messrs. McCarthy and Lilburn, Scottish Provident Buildings, Belfast. (c) 5gns. (e) October 25.

NORTHUMBERLAND C.C. (a) Adaptation of "Lyndhurst" and "Yearsley", Delaval Road, Whitley Bay, for use as a further education centre. (b) County Architect, County Hall, Newcastle upon Tyne, 1. (d) October 18.

RUNCORN U.C. (a) 14 bungalows and 28 houses in Windsor Grove. (b) Council's Surveyor, Town Hall. (c) 2gns. (e) November 2.

ST. ALBANS C.C. (a) Erection of 4 shops, 4 flats and 8 garages at Westfields estate. (b) City Engineer, 16 St. Peter's Street. (c) 2gns. (e) October 22.

SAFFRON WALDEN R.C. (a) Two bungalows at Birchanger. (b) Council's Clerk, Council Offices, Debden Road. (e) October 27.

SCOTLAND—BRIDGE OF ALLAN BURGH COUNCIL. (a) Several works in connection with the erection of 18 houses at Castlevue Drive, Blackdub—Sixth Development. (b) Town Clerk, Burgh Chambers. (d) October 15.

SCOTLAND—CAITHNESS C.C. (a) Erection of a new primary school at Wick. (b) County Architect, County Offices, Wick. (e) November 12.

SMETHWICK B.C. (a) Erection of additions and adaptations to existing buildings at the Housing Estates Department. (b) Borough Engineer, Council House, in writing. (c) 2gns, by cheque payable to The Borough Treasurer. (e) November 1.

SOMERSET C.C.—EDUCATION COMMITTEE. (a) (1) Yeovil Girls' High School; (2) Keynsham Wellsway primary school. (b) County Architect, Park Street, Taunton, with an assurance that applicant has necessary financial and material resources and organization to undertake the work. (c) 2gns each contract. (d) October 15.

SOUTH SHIELDS B.C. (a) 97 houses on Whiteleas estate. (b) Borough Engineer, Town Hall. (c) 2gns. (e) November 6.

SWANSEA B.C. (a) Cloakroom and lavatory accommodation at Neath Road School, Morriston. (b) Borough Architect, The Guildhall. (c) £2. (d) October 19.

WEST KENT MAIN SEWERAGE BOARD. (a) Erection of a laboratory at the sewage purification works, Long Reach, Dartford, Kent. (b) Board's Secretary, 20 Blyth Road, Bromley, Kent. (c) 2gns. (e) October 29.

WIRKSWORTH U.C. (a) 12 houses with consequent works. (b) Mr. J. L. Bakewell, 25 Chapel Street, Belper. (c) 2gns. (e) November 3.

For the eradication of
DRY ROT
and
WOOD-BORING INSECTS

you cannot improve on

Reskol Fungicide
Wykamol Insecticide

or the specialist advice
and guaranteed treatment
services provided by

RICHARDSON & STARLING LTD.

TIMBER DECAY SPECIALISTS

Members of the
British Wood Preserving Association
(Dept. AB), Hyde St., Winchester.
Tel: 5001/2

London Office:

The Timber Decay Enquiry Bureau,
6 Southampton Place, W.C.1.
Tel.: HOLborn 3555-6

WRITE FOR FREE BROCHURE

**UNBREAKABLE
PLASTER VENTILATORS,
LOUVRES AND GRILLS**

Full Particulars & Sample on request from

COZENS VENTILATORS LTD.

2 Kingswood Road, Penge, London, S.E.20
SYDENHAM 8575

**DENNISON
KETT
& CO. LTD.**

**ROLLING
SHUTTERS**

**COLLAPSIBLE GATES
& GRILLES :: IRON DOORS
STAIRCASES :: LIFTS**

**KENOVAL HOUSE
226-230, FARMERS ROAD
LONDON, S.E.5. Phone: RELiance 4266**

don't just say mastic
specify **SECOMASTIC**

Secomastic Ltd. Bracknell, Berks. Tel: Bracknell 310

PLACED

Notes on contracts placed state locality and authority in bold type with (1) type of work, (2) site, (3) name of contractor and address, (4) amount of tender or estimate. † denotes that work may not start pending final acceptance, or obtaining of licence, or modification of tenders, etc.

LONDON S.E. (1) Nine-storey flats for St. Thomas's Hospital Governors. (2) Royal Street, S.E.1. (3) Wates Ltd., 1258 London Road, Norbury, S.W.16. (4) £250,000.

ATOMIC ENERGY AUTHORITY. (1) 74 houses for scientists. (2) Harwell, Berks. (3) F. J. Minns and Co. Ltd., St. Aldate's, Oxford. (4) £500,000.

LEEDS CORPORATION. (1) 126 houses. (2) Various estates. (3) West and Sons (Leeds) Ltd., Westley Road, Leeds.

LONG EATON U.D.C. (1) 174 houses and bungalows. (2) Sawley. (3) F. Perks and Son Ltd., Bridge Street, Long Eaton, Notts. (4) £239,250.

LEEDS. (1) New buildings at Leeds Grammar School. (3) J. H. Wood and Co. Ltd., St. Columba Street, Leeds.

NORTHAMPTON E.C. (1) Stage 2 of Grammar School for Girls. (3) Simcock and Usher Ltd., of Northampton. (4) £66,762.

RAWTENSTALL CORPORATION. (1) 75 houses. (2) Balladen Estate. (3) A. Spencer and Sons Ltd., of Accrington. (4) £89,351.

MIDDLESBROUGH. (1) Erection of secondary school. (2) Prissick Farm. (3) A. V. Clerey and Sons, 14 Frederick Street, Sunderland. (4) £152,489.

BRIGHTLINGSEA U.D.C. (1) 52 houses and shops. (2) Council's estate. (3) T. J. Archer and Co., Great Yeldham. (4) £75,688.

BRENTFORD. (1) Extensions to Phoenix Works, for R. B. Pullin and Co. Ltd. (2) Great West Road. (3) Gee, Walker and Slater Ltd., 100 Park Lane, London, W.1. (4) £188,000.

WORCESTERSHIRE C.C. (1) Extensions to Four Pools Lane School. (2) Evesham. (3) Espley and Co. Ltd., Evesham, Worcs. (4) £86,250.

LANCASHIRE C.C. (1) School (C. of

E.). (2) Cartmel Priory. (3) Thompson and Jackson Ltd., of Lancaster. (4) £94,463.

HEREFORDSHIRE C.C. (1) First instalment of college. (2) Broadlands. (3) John Williams and Co. (Cornwall) Ltd., St. Austell, Cornwall.

CUCKFIELD R.D.C. (1) 42 flats. (2) Hassocks. (3) Saunders (Contractors) Ltd., London Road, Burgess Hill, Sussex. (4) £60,798.

LONDON COUNTY COUNCIL. (1) Day school for delicate children. (2) Avenue Road, Hampstead. (3) Howard and Co., 11 Broad Court, London, W.C.2. (4) £54,708. (1) Extension to Haverstock School. (2) Hampstead. (3) Poolman (Builders) Ltd., Hendon, N.W. (4) £27,415.

ASHBY-DE-LA-ZOUCH COUNCIL. (1) 90 houses, 2 shops. (2) Worthington. (3) George Wimpey and Co. Ltd., Wollaton, Nottingham. (4) £161,818.

LYTHAM ST. ANNE'S B.C. (1) Crematorium. (2) Park Cemetery. (3) Keenan and Yates Ltd., Lord Street, Lytham St. Anne's. (4) £35,000.

PORTSMOUTH CORPORATION. (1) Rebuilding war damaged wing, Foster Hall. (3) Direct labour. (4) £24,189.

CHESHIRE C.C. (1) Secondary school. (2) Macclesfield. (3) Cooper Bros. and John Clayton Ltd., Catherine Street, Macclesfield.

HEYWOOD B.C. (1) 96 flats. (2) Hardfield. (3) J. Hobson and Sons Ltd., Summer Street, Rochdale.

ESTABLISHED OVER 100 YEARS
J. W. GRAY & SON LTD
 1 PRINCETON STREET
 BEDFORD ROW, W.C1
LONDON & SALISBURY
 CHA 8701*
 SAL 2750
CHURCH SPIRE RESTORERS

RINGMER BUILDING WORKS, LTD.

BUILDERS & CONTRACTORS

Joinery Specialists



RINGMER : LEWES : SUSSEX

Telephone: Lewes 300

Gone to earth...

without danger of corrosion—Kontite GUNMETAL Underground Fittings are of full bore leaving waterways unrestricted. Ball and socket effect allows for limited misalignment between tube and fitting and tests have proved that the joint is stronger than the tube itself.

★ Write for full report on Kontite Underground Fittings.



UNDERGROUND FITTINGS

KAY & COMPANY (ENGINEERS) LTD., BOLTON BRASS WORKS, BOLTON
 London Office: 36 VICTORIA STREET, S.W.1. Tel: ABBEY 2144. Grams; "KONTITE" SOWEST, LONDON



Write to the SURFEX FLOORING COMPANY LIMITED makers of the World's finest Floorings — including INDUSTRIAL VINYL SURFEX for heavy foot and truck traffic, and POLYFEX domestic and office flooring.

KORODUR Heavy Industrial Flooring is a unique, pure quartz composition. Once laid it is permanently unaffected by exceptionally heavy wear including the regular passage of tracked or other massive traffic, and will bear pressures of up to sixty tons with ease. KORODUR is impervious to fire, oils, petrol, water and a wide variety of chemicals and acids. Full test reports on KORODUR are available on application to the SURFEX FLOORING COMPANY LIMITED who are the sole agents for KORODUR. KORODUR can be machine laid by our own team of experts.

KORODUR
HEAVY INDUSTRIAL FLOORING

SURFEX FLOORING CO. LTD. 48 HIGH ST • CAMBERLEY • S • SURREY • Tel: CAMBERLEY 2263

NEW DAY

Range of Matched Accessories with many new features

Make sure you have our New Brochure
NEWDAY ELECTRICAL ACCESSORIES LIMITED
 136/8 MARY ST., BIRMINGHAM, 12. Tel.: Calthorpe 2621
 One of the Companies associated with Southern Areas Electric Corporation Ltd.

There's no stopping **BANBURY**


The new Battery Garage is the latest proof of Banbury leadership.

This modern, enthusiastic Company is never satisfied—but always striving for better and better products. The new Battery Garage is the latest example of Banbury progress. Redesigned moulded front gives streamlined new look. All external joints are roll-capped, sealed and lapped for complete weather proofing. Side barge boards add "finish" and extra weather proofing. Unique Banbury "easy lift" roof trusses, complete with new flush-domed clips, add the final touch to a brilliant design—and at no extra cost! And don't forget Banbury Batteries all have the perfect aluminium "Glide-Over" Doors: attractive weatherboard design. Every unit vibrated and steel reinforced. Easiest self-assembly. Credit sales facilities of course. Free delivery—wide area. Batteries for 2 cars or 102. Make that odd piece of land earn money.

Write now for full details of Banbury Batteries and single or double Garages and of free site lay-out service. Made by the makers of the famous Banbury Garages. For super speedy erection we are the experts—may we quote you. Buy a Banbury—you'll be as proud of it as we are!

PORTABLE CONCRETE BUILDINGS LTD., Ironstone House, Adderbury East, Nr. Banbury, [Oxon.
 DHB/2729A

Tel.: Adderbury 331/2/3



*Specified
for the best bathrooms*

THE **LEDA** HOT WATER TOWEL RAIL

A bathroom fitted with a 'Leda' hot water towel rail always wins approval—for its owner, for its designer and for its builder. This rail gives the bathroom a luxurious look, and the luxurious feeling that comes from constant dry, well-aired towels and constant warmth. The 'Leda' both in design and specification is undoubtedly the finest hot water towel rail on the market.


- *Patented method of assembly which ensures leakproof joints.*
- *Two air release valves operated by a coin—no keys to lose.*
- *High standard chromium plating on nickel.*
- *Available in two and three rail models to suit every bathroom.*
- *Individually tested at 120 lb. per square inch air pressure in hot water.*

See the Leda at the Building Centre, Store Street, London, W.C.1, or write for descriptive leaflet to:—

W. C. YOUNGMAN LIMITED

Makers of LEDA Matched Bathroom Accessories.

MANOR ROYAL, CRAWLEY, SUSSEX Telephone: CRAWLEY 1234 (5 lines)



Facts about

plastaweld

Another **MANGER** product

PERMANENT BONDING FLUID FOR GYPSUM PLASTERS



What it is: PLASTAWELD is a non-toxic fluid used straight from the can. Does NOT require stippling or binding with sand.



What it does: Permanently bonds gypsum plasters to all sound surfaces, however smooth, WITHOUT PRELIMINARY HACKING.



How much it costs: 46/9 per gallon for 70 to 120 sq. yards coverage, according to type of surface.



Advantages: NO HACKING, NOISE, DUST OR DIRT. Very simple to apply with brush or spraygun.



How we can help: Our technical department is at your service to assist in particular problems.

Technical Representatives
are ready to call on you
or visit your sites.

Telephone Clissold 5307
(4 lines) or write to:
Dept. AB

**J. MANGER
& SON LTD.**


57d KINGSLAND
HIGH STREET
LONDON E.8

Phone: CLissold 5307/10



SOLID FUEL

from 250,000 B.t.u.



D.1000. Burns wide range of solid fuels, thermostatic control, can be fitted with automatic conveyor and ash disposal units. Capacity 1 million B.t.u.

TRIANCO

automatic boilers

a boiler for every need

Central Heating and Hot Water Supply for factories, offices, blocks of flats, institutions, hospitals, cinemas etc.

HIGH THERMAL EFFICIENCY AND LOW OPERATING COSTS

Let Trianco engineers assist and advise you on the best type of boiler and installation. Trianco now provide a complete range of boilers burning solid fuel or oil and there is a capacity for every need.


Essence of all Trianco boilers is their automatic operation with high efficiency and low operating costs, and they incorporate latest developments in techniques for rapid heat exchange and completely smokeless combustion.

SOLID FUEL DOMESTIC BOILERS

from 50,000 B.t.u. capacity incorporating gravity feed, automatic thermostatic control declinking without dust.

OIL

from 400,000 B.t.u.



Trianco Oil Fired Boiler capacity 400,000 B.t.u. Fully automatic. Efficiency over 80%. Can be installed as double or triple unit.

Write for brochures and full details to :

TRIANCO LTD. (Heating Division) IMBER COURT, EAST MOLESEY, SURREY. Emberbrook 3300

ALFOL FOILS FOR



THERMAL INSULATION OF WALLS, ROOFS, CEILINGS

IN DOMESTIC & INDUSTRIAL BUILDINGS
CANTEENS, SITE OFFICES & SCHOOLS


- Economical in cost
- Negligible weight
- Easy and quick to apply
- Perfectly clean
- Efficient in use
- Compact to store and handle
- Effective moisture vapour barrier

The bright reflective surfaces of the Alfol Foils make this system of insulation extremely effective against the entry of Solar Heat through roofs in Tropical Climates

Technical Data and Quotations given on receipt of details of any particular construction

ALFOL INSULATION LTD.
25 CAXTON STREET - LONDON - S.W.1
ABBAY 7150

FIRE AUTOMATICALLY SEALED



WITH

CURFEW FIREPROOF DOORS

And protect against burglary with
COLLAPSIBLE GATES, ROLLING DOORS & GRILLES
CURFEW DOORS & SHUTTERS LTD.
CURFEW WORKS, ANCOATS, MANCHESTER, 4

Telephone: COLlyhurst 3908

Beacon Works, Strawberry Vale, TWICKENHAM, Middlesex.
Telephone: POPEsgrove 0794

The Quality Felts Roofings and Dampcourses



BLACKWELLS
STANDARD BITUMEN
ROOFING
PURE BITUMEN
DAMP COURSES
UNDERSLATING FELTS
SHEETING AND
PACKING FELTS

For over 50 years Blackwells have been making Felts, Roofings and Dampcourses of outstanding quality and value. To-day these products provide Architects, Builders and Handymen with an unsurpassed range.

The same high standard of workmanship and materials goes into the roofing work which Blackwells carry out under contract. May we quote you for your requirements?



BLACKWELLS
REINFORCED
UNDERLINING
No. 50
A BITUMEN IMPREGNATED
FELT REINFORCED WITH
A HESSIAN BACKING
UNTEARABLE

Write for samples & literature

BLACKWELLS & NATIONAL ROOFINGS LTD
MEMBER OF THE BRITISH PLASTER BOARD ORGANISATION

ALTRINCHAM · CHES.
TEL: ALTRINCHAM 2641



ERITH · KENT
TEL: ERITH 2641

STEELWORK to Architects' Specification



Length 300ft

Span 101ft - 6in

Pitch 17 deg

Architects: Fowler Grove & Haggart, Southampton

After half a century of stagnation, steel is once again taking its place as the pre-eminent structural medium. In single and multi-storey work alike new forms and new design and fabrication methods take the place of the old. Conder is in the forefront of these developments.


Illustrated booklet with useful data on costing, roofing materials and insulation sent on request.



CONDER ENGINEERING COMPANY LTD
WINCHESTER : HANTS : Tel. 5095

Midlands Branch: PEEL HOUSE, LICHFIELD STREET, BURTON-ON-TRENT

TEL: 4690



Electricity from Nuclear Energy

A 20-year development programme

Britain's nuclear power station construction programme will go far to offset the growing shortage of coal in the next two or three decades.

The First Ten Years

Work will start on the first two nuclear power stations in 1957. These will each have two gas-cooled reactors and the stations will be in operation by 1960/61. Two further gas-cooled reactor stations — each housing two reactors of improved type — to be begun in 1958/9 will come into service by 1963. The output of these four stations will be between 400,000-800,000 kilowatts.

The construction of two groups of four stations each will begin in 1960 and 1961/2 and they will be supplying electricity to the Grid by 1963/4 and 1965 respectively. The first group of stations will probably

have one gas-cooled reactor each. The second will probably utilise liquid-cooled reactors — one high-rated reactor each. These stations will add well over 1,000,000 kilowatts to the nation's power resources.

The Second Ten Years

By 1975, it is anticipated that nuclear reactor power stations in Britain will have an aggregate installed capacity of between 10,000,000 and 15,000,000 kilowatts. Since these stations will be operated as base load stations working at full output for twenty-four hours a day they will be responsible for possibly half the units generated in the country.



In ten years' time—1,500,000 to 2,000,000 kilowatts of nuclear power. In twenty years' time—10,000,000 to 15,000,000 kilowatts of nuclear power, equivalent to 40-50,000,000 tons of coal a year.



GOLMET


Aluminium Garage

ROLL DOORS & SHUTTERS

SILENT OPERATION

QUICK ERECTION

CORROSION RESISTING



(Inside View)

Golme Roll Doors are made from a single sheet of high tensile aluminium suitably corrugated. The door opens upward smoothly and easily and is self-coiling. Golme Roll Doors are ideal space savers for domestic garages, service stations, warehouses, vehicle depots, agricultural buildings, etc.

Size: 7ft wide by 6ft 8in high £23 - 0 - 0
Size: 8ft wide by 6ft 8in high £26 - 0 - 0

YOUR INQUIRIES WELCOMED

PHONE: BLACKfriers 8282 (26 lines)

BAXENDALE & CO. LTD.

MILLER STREET, MANCHESTER 4

Also at LIVERPOOL, EDINBURGH, DUBLIN, LANCASTER, LEEDS & BLACKPOOL

FLOOR covering

Can-Tile liquid floor coating for canteens, hospitals, shops, factories, toilets.

Costs 20% of lino.

Write:

DOHME

167 Victoria St., London, S.W.1

Telephone: VIC 1414 (8 lines)


CAN-TILE

CAN-TILE

- 1** Easy to fix—can be sawn and nailed without drilling.
- 2** Easy to handle—weighs only 8 oz. per sq. ft.
- 3** Shatter-proof—take a walk across it and prove it for yourself!
- 4** Can be used with any standard roofing profiles in **Standard Purlin Spacings.**

Available for most standard profiles and in lengths from 36" to 120".


RILITE
CORRUGATED GLASS FIBRE SHEET



WRITE FOR SPECIMENS
AND QUOTATIONS

ANOTHER **RIL** PRODUCT

RUBBER IMPROVEMENT LTD. • WELLINGBOROUGH, NORTHANTS • WELLINGBOROUGH 2218



'Helmsman' Twin Locker Installation
for 22 persons; occupying wall space of
13ft. 9in. x 6ft. high, floor area of
13½ sq. ft.

**Save MONEY and
37½% WALL
SPACE ON
CLOTHES
STORAGE!**

Each Twin Locker Unit provides separate accommodation for the clothing and personal belongings of two persons. Fitted with modern streamlined SLIDEX Handle with 3-Point Latching, lockable with padlock. Standard size: 72in x 15in x 12in deep. Wide choice of colours and other sizes. **LIST PRICE £4 18s 6d** (in nests of 3) per person. (£9 17s 0d per Twin Locker.) (Traditional 6-lever Lock in lieu or in addition if required.) Other 'Helmsman' Products: Shelving: Open-type; solid sides; Cupboards; Bin Units; Cabinets; All-steel Desks. Full details gladly sent on request, or phone Mr. Quin at Larkwood 4411.

Helmsman- TWIN TYPE
STEEL CLOTHES LOCKER (Patent No. 699842)

W.B. BAWN
& COMPANY LIMITED

Discounts for quantities; special quotations for complete installations; prompt delivery; normal commercial credit terms to business undertakings.

**BRYON WORKS, BLACKHORSE LANE,
LONDON, E.17.**

Telephone: LARKWOOD 4411/4



**VITAL
TO GOOD
HEALTH**

Hygienic sanitation
for no-mains sites

DESTROL

- FULLY FLUSHING
- NO MANUAL EMPTYING
- TOWN TYPE SANITATION
- ANYWHERE - UNIQUE
- FULLY AUTOMATIC



With these completely self contained sewage disposal units better living conditions and a higher standard of health can be enjoyed by everyone in remote rural areas away from mains services.

DESTROL FLUID—a new and unique perfumed disinfectant and precipitant which rapidly promotes disintegration and is harmless, non-corroding and permanently potent.

DESTROL SALES LTD., (Dept. 153) 402 Salisbury House, London, E.C.2



Trial Borings

to prove strata ...and bore holes for
water supplies, pumping plant, etc.

Undisturbed Samples Provided if Required

JOHN THOM

Ltd
CANAL WORKS • ECCLES • MANCHESTER

Telephone: THOMP 2181, 2182
Telegrams: ECCLES 2281-2-3

Telephone :
ENfield 4877/8

Telegrams :
Quality, Enfield

SHUTTER CONTRACTORS LTD.

LINCOLN WORKS

ENFIELD


MANUFACTURERS OF

Quality

**ROLLING SHUTTERS
IN STEEL, WOOD &
ALUMINIUM ALLOY
FOR ALL TYPES OF BUILDINGS**

APPROVED MANUFACTURERS TO
F.O.C. AND L.C.C. REQUIREMENTS

CONTRACTORS TO
H.M. GOVERNMENT—ALL DEPARTMENTS
PUBLIC UTILITY COMPANIES, COUNCILS
PRINCIPAL RAILWAYS, INSTITUTIONS
Etc.



Broadsheet
available

TUCKER & EDGAR

Berkley Road, London, N.W.1.
PRImrose 5483


ACROW

-THE ORIGINAL

UP-AND-OVER**GARAGE DOOR****-AND STILL THE BEST**

Because the GEAR:—

- ★ takes up least room inside garage; projects only 3 inches from wall face; needs no extra room for counter-balance weights.
- ★ is quickest to fix; and requires least number of fixings to garage.
- ★ is adaptable to the widest range of conditions and is not affected by irregular dimensions.




We supply GEAR SEPARATELY; or GEAR & STEEL DOOR

For fully descriptive literature and prices write or 'phone to:—


ACROW (ENGINEERS) LTD.
SOUTH WHARF, PADDINGTON, LONDON, W.2
Telephone: AMBASSADOR 3456 (20 lines)

Branches at:

BIRMINGHAM • LEEDS • BRISTOL • MANCHESTER • LIVERPOOL
NEWCASTLE • SOUTHAMPTON • SWANSEA • GLASGOW

**INSIDE INFORMATION...**

By his discovery of the X-ray, Professor Röntgen took much of the guesswork out of modern surgery. Röntgen rays have also become of inestimable value in industry and a great debt is owed to this famous pioneer. In industry also, Penfold have proved their worth as pioneers. They have introduced improved Galvanised Chain Link Fencing, Stainless Steel Chain Link Fencing for "difficult" areas and now—PRE-STRESSED CONCRETE POSTS. Manufactured by an exclusive Scandinavian method of proved design they possess a strength several times that of the ordinary reinforced concrete post. In consequence straining struts are unnecessary—excavated post holes can be smaller and require less concrete—the posts are slimmer and present a neater appearance without loss of effectiveness—their life is well-nigh unlimited. The cost?—no more than ordinary reinforced concrete posts! We will gladly send you further particulars on request.

**PENFOLD FENCING & ENGINEERING LTD.**

IMPERIAL WORKS : BALMORAL ROAD : WATFORD : HERTS
Telephone: Watford 2241 Telegrams: "Penfold, Watford"



Batley multiple garages can be erected in any number in one block at a fraction of the cost of brick structures. Ideal for Housing Estates, Public Utilities, Hotels, etc. As private lock-ups they provide an unequalled investment.

Prices from £55. Attractive deferred terms.

- ERECTION SERVICE AVAILABLE.
- CHOICE OF HINGED OR 'UP & OVER' DOORS
- PURCHASED BY OVER 220 COUNCILS.
- 3 YEARS' GUARANTEE.
- 5 YEARS' FREE FIRE INSURANCE.

SIZES: Lengths 13' 8", 16' 4" or 19'.
Clear height 6' 3" or 7' 9".

FREE DELIVERY IN ENGLAND & WALES.

Write for illustrated Brochure to

ERNEST BATLEY LTD.,

96, Colledge Road, Holbrooks, Coventry,
Telephone : 89245/6.

ACTUAL MANUFACTURERS OF
EXTERIOR GRADE

PLYWOOD and VENEERED PLYWOOD

SPECIALITY — PANELLING
TO
ARCHITECTS' SPECIFICATIONS

RELIABLE PLYWOOD COMPANY LIMITED
PROGRESS WORKS, WARBURTON STREET, LONDON, E.8
Telephone: Clissold 3496/7 Telegrams: Reliably-Hack, London

Architecture as a Career

A Practical Handbook for Students

By MAURICE E. TAYLOR, M.T.P.I., A.R.I.B.A., F.I.L.A., F.R.I.A.S., F.S.A.S.COT., R.I.B.A. DIST. T.P., A.A. DIP. OF PLANNING. Offers practical, comprehensive information on every aspect of the subject, and discusses many problems the intending architect is likely to encounter. The various methods of approach to the architectural profession, regulations and documents concerning the most important R.I.B.A. examinations, and the many scholarships and prizes open to students are all described in detail. This book, published for *The Architect & Building News*, will prove an invaluable guide to all who would enter the profession.

10s 6d net. By post 11s 2d

Obtainable from all booksellers or from:

THE PUBLISHING DEPT., DORSET HOUSE, STAMFORD STREET, LONDON, S.E.1

SIGN MAKERS

SIGNCRAFTS LTD

COBOURG WHARF, COBOURG ROAD
LONDON, S.E.5

Telephone : Rodney 4433



There is nothing the same as Uni-Bond. Beware of substitutes. Uni-Bond is guaranteed.

it's **FIXED** with

BOND-ANYTHING-TO-ANYTHING

Here's the most astounding bonding agent ever contrived. No more hacking for keying. Uni-Bond will bond cement/sand to old surfaces, of tile, rendering, compo, asphalt, also to Timber, Asbestos, Zinc, Lead, Cloth to Cloth, Glass. In fact it will Bond Anything To Anything to each and one another. For inside and external use.

We guarantee the material. It is quite impossible for any Works Engineer, Architect, Builder, Surveyor, not to have a use of some kind for Uni-Bond. Uni-Bond is ready for use—no mixing. Will store for up to two years, and is used cold.

Uni-Bond



SEND
FOR THIS
BROCHURE
TO-DAY!

LIQUITILE SUPPLY CO. (Dept. IEN) 48 HIGH STREET · CAMBERLEY · S · SURREY Telephone : Camberley 2263. Ext. 2




SWEDISH MADE
MASONITE
SEMI-HARD
QUARTERBOARD

*it is sold in 9'x 4' sheets
 * Packed 15 sheets to a crate*

For notices, maps, photos, drawing boards.
 Ideal for anything that requires pinning up.

MASONITE
 MADE IN SWEDEN

Standard - Tempered - Enamelled - Plastic - Leatherboard
 MASONITE LIMITED, BEVIS MARKS HOUSE, BEVIS MARKS, LONDON, E.C.3. Telephone: AVenue 2846




DON'T BE CAUGHT OUT ABOUT STONE COVERING PAINT

**OUR BOOK WILL TELL YOU
 HOW
 WHEN
 and WHERE
 TO APPLY
 THIS
 MATERIAL**


Stic B is a decorative and waterproofing treatment which can be applied with a minimum of trouble to new or old concrete and cement rendering, and other building surfaces!

Our product has been tested by the British Government Building Research Station, and the results which were obtained were described in our technical brochure. This information is available to architects and builders, who are invited to write for a copy.

Some recent Stic B contracts include Flats at Paddington, Lambeth, Leicester, Mitcham and Fulham, and Central Hospital, Kumassi, Gold Coast, etc.



Coarse Stipple.



Fine Stipple.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD, VAUXHALL, S.W.8
 Telephone: RELiance 5566

OFFICIAL ANNOUNCEMENTS

APPOINTMENTS • CONTRACTS • TENDERS

Rate 1/6 per line, minimum 3/-

Close for press 1st post Monday for following Thursday Issue

APPOINTMENTS

AIR Ministry Works Design Branch requires in London and Provinces Architectural Assistants experienced in planning/preparation of working drawings and details for permanent and semi-permanent buildings.

Salaries in London up to £925 p.a. (men) and £831 (women). Lower in Provinces. Starting pay dependant on age, qualifications and experience. Long-term possibilities with promotion and pensionable prospects. Five-day week. 3 weeks' leave a year. Liability for overseas service. Normally natural born British subjects. Write stating age, qualifications, employment details, including quoting Order No. Borough 1.900. [2674]

APPLICATIONS are invited for appointment to the post of

ARCHITECT
in the Lands and Works Department,
GIBRALTAR.

The post is permanent and pensionable and on probation for two years. Salary scale £720x£840 then £940x£1,200 per annum. Entry into the scale will be in accordance with post graduate experience. Leave on full salary and return passages to U.K. for officer and wife granted once every two years.

Candidates must be A.R.I.B.A. and have good knowledge of design and construction. Duties will include design and execution of building projects. The successful candidate will work under the Commissioner of Lands and Works and is required to assume duties early December, 1956.

Unfurnished quarters and basic furniture, if available, will be provided at rents not exceeding 10% of salary and 3% of value respectively.

Applications stating qualifications, age, previous experience and enclosing testimonials, a birth certificate and a recent photograph should reach the Colonial Secretary, Gibraltar, not later than November 8, 1956. [2773]

ATOMIC ENERGY RESEARCH ESTABLISHMENT HARWELL

has a vacancy for an **ARCHITECTURAL ASSISTANT** to prepare sketch schemes, working drawings and details for works of extension, conversion and adaptation to existing buildings. The range of work is very wide and many aspects are of a novel nature.

Applicants should be of at least Inter. R.I.B.A. standard and have had at least three year's experience in an Architect's office.

Salary: £908 (at age 21)—£795 p.a. (Highest starting salary £695).

Contributory Pension Scheme, five day week, excellent working conditions and generous leave allowance.

Note: Married officers living outside the Establishment's transport area will be eligible for housing under Authority arrangements or, alternatively, substantial assistance towards legal expenses incurred in house purchase will be available.

Send postcard for application form, which must be returned by October 22, 1956 to Establishment Officer, A.E.R.E., Harwell, Didcot, Berks, quoting reference 624/184. [2765]

BOROUGH OF ROYAL LEAMINGTON SPA

ARCHITECTURAL DRAUGHTSMAN, GRADE II

APPLICATIONS are invited for the above post in the Borough Engineer's Department within the salary scale of A.P.T. II.

Candidates should be a competent draughtsman with a knowledge of building construction. Experience in the supervision of outside works would be an advantage.

Completed forms of application, which are obtainable from the Borough Engineer, should be returned to reach his office not later than October 24, 1956.

JAMES N. STOTHERT,
Town Clerk.

Town Hall,
Leamington Spa. [2766]

COUNTY BOROUGH OF EAST HAM

JUN. ASST. PLANNING OFFICER

GRADE I £830-£610. Borough Engineer's Department. Plus London Weighting. Salary above minimum and subsistence may be paid subject to conditions. Details and form from Town Clerk, E.6. Closing date October 22, 1956. [2771]

APPOINTMENTS—contd.

COUNTY BOROUGH OF GRIMSBY

BOROUGH ENGINEER AND SURVEYOR'S DEPARTMENT

APPOINTMENT OF SENIOR PLANNING ASSISTANT

APPLICATIONS are invited for the appointment of a Senior Planning Assistant in the Borough Engineer and Surveyor's Department at a salary in accordance with Grade III of the A.P.T. Division of the National Scale of Salaries (£640 per annum increasing by annual increments of £25 to £765 per annum.)

The appointment will be subject to the conditions of service of the National Joint Council, terminable by one month's notice on either side, and to the provisions of the Local Government Superannuation Acts. The successful candidate will be required to pass a medical examination.

Applicants should be suitably qualified by education, with experience of planning control and work involved in the preparation and presentation of Comprehensive Development Maps. Urban Estate experience would be an advantage.

Housing accommodation can be provided for the successful candidate, if married.

Applications giving details of age, qualifications and experience, together with copies of two recent testimonials, must be suitably endorsed and delivered to the undersigned not later than first post on Saturday, October 20, 1956.

J. V. OLDFIELD, M.Inst.C.E., M.T.P.I.,
Borough Engineer and Planning Officer,
Municipal Offices,
Town Hall Square,
Grimsby.

September 1956. [2756]

GOVERNMENT OF NORTHERN IRELAND

ARCHITECTURAL ASSISTANTS

APPLICATIONS are invited from Architectural Assistants with recognised training and fair experience for unestablished posts in the Chief Architect's Branch, Directorate of Works, Ministry of Finance.

The salary scale including pay supplement is £460 rising to £761. The inclusive starting pay of candidates who have passed the R.I.B.A. Intermediate Examination will be £596. Entry points for other candidates will be fixed in relation to their ages, e.g., £469 at age 21—£549 at age 25 or over. This scale is under review.

Preference will be given to candidates who served in H.M. Forces in the 1914-18 or 1939-45 wars, provided that such candidates are, or within a reasonable time will be, able to discharge the duties efficiently.

Application forms may be obtained from the Director of Establishments, Ministry of Finance, Stormont, Belfast. [2776]

BOROUGH OF ELLESMERE PORT

APPOINTMENT OF ARCHITECTURAL ASSISTANT

APPLICATIONS are invited from experienced men for the above appointment on the permanent salaried staff of the Borough Engineer and Surveyor. Applicants must have completed their professional training and have had a good general architectural experience, preferably in a Local Government Department, and preference will be given to those who have passed the preliminary examination of the R.I.B.A. The post is a superannuated one within Grade II—III (£596—£765 per annum) of the A.P.T. Division of the National Salary Scales. A weekly tenancy of a Council house will be offered to the successful candidate on appointment if he reasonably requires accommodation.

Applications, stating age, qualifications, experience and giving the names and addresses of two referees, must reach me by not later than Monday, October 29, 1956.

R. J. BERNIE,
Town Clerk.

Municipal Offices,
Ellesmere Port,
Cheshire.
October 1, 1956. [2768]

APPOINTMENTS—contd.

COUNTY BOROUGH OF SOUTHEND-ON-SEA EDUCATION COMMITTEE

Principal:
T. L. MORGAN, M.Sc., A.M.I.C.E., A.M.I.Struct.E.

APPLICATIONS are invited for the following posts:

Studio Master in the School of Architecture (Asst. Grade B). Salary scale £650 x £725—£1,025 with additions for training, graduation and good honours degree.

Further particulars and forms of application may be obtained from the undersigned (stamped addressed foolscap envelope).

Completed forms should be returned within 14 days to the Principal, Municipal College, Victoria Circus, Southend-on-Sea.

D. B. BARTLETT,
Chief Education Officer.

Education Office,
Warrior Square, Southend-on-Sea. [2767]

BANFF COUNTY COUNCIL invite applications for the post of County Architect and Planning Officer on salary scale £1,415x£252—£1,675 per annum. J.N.C. for Chief Officials (Scotland) conditions apply and a car allowance is payable under the Council's scheme.

Applications should have extensive experience of local authority architectural work, particularly school work, as there is a large capital programme to be undertaken and should be familiar with planning procedure to the stage of submission of the Development Plan and dealing with planning applications.

Applications stating age, qualifications and experience with copies of three recent testimonials to be lodged with the County Clerk, County Buildings, Banff, by October 19, 1956. [2770]

DOWSETT Engineering Construction Limited require Quantity Surveyors for extensive Building and Civil Engineering Contracts in the North East of England. Good allowances and salaries will be paid and permanent superannuated positions may be offered to selected personnel after a probationary period. Written applications will be treated in strict confidence and should give age, qualifications, personal details as to education and previous appointments held, with remuneration received, to Director, 50/52 Scotswood Road, Newcastle upon Tyne, 4. [2754]

TUITION

COURSES FOR R.I.B.A. EXAM

POSTAL tuition in any subject or for full syllabus of Inter. Final or Special Final, including Professional Practice, Revision Courses arranged to meet individual requirements. Courses also available in general educational subjects for G.C.E., R.I.C.S. Preliminary, etc.

THE ELLIS SCHOOL OF ARCHITECTURE
(Principal: A. B. Waters, F.R.I.B.A.) 103D Old Brompton Road, London, S.W.7 (KEN 4477), and at Worcester. [0789]

MISCELLANEOUS SECTION

RATE: 1/6d. per line, minimum 3/-, average line 6 words. Each paragraph charged separately.

BOX NOS. add 2 words plus 1/- for registration and forwarding replies which should be addressed c/o "The Architect & Building News," Dorset House, Stamford Street, London, S.E.1.

PRESS DAY, Monday. Remittances payable to Iliffe & Sons Ltd., Dorset House, Stamford Street, London, S.E.1.

No responsibility accepted for errors.

ARCHITECTURAL APPOINTMENTS VACANT

ARCHITECTURAL Assistants required, approaching A or at Intermediate stage. Up to £550 p.a.—D. Plaskett Marshall, F.R.I.B.A., 99 Gordon Square, W.C.1. MUS 7176/7. [2742]

ARCHITECTURAL Assistant of A.R.I.B.A. standard or near with experience of traditional building methods as well as modern techniques urgently required. Apply: Marshall Sison, A.R.A., F.R.I.B.A., F.S.A., Farm Hall, Godmanchester, Hunts. [2762]

ASSISTANT Architects required in busy and varied Practice with Offices London, West Riding of Yorkshire, and Middlesbrough as follows:

(a) Senior Architects to be Associates of the R.I.B.A. with considerable experience, preferably in Schools, Commercial or Industrial work. Salary £1,000 per annum according to experience. (b) Qualified Assistant Architects with minimum two years' Office experience. Salary £450 to £480 per annum according to experience. (c) Assistant Architects Inter-final standard. Salary £550 to £650 per annum according to experience.

Pension scheme available and good prospects for promotion. Apply with full particulars to J. G. L. Poulton, Chartered Architect, 29 Ropergate, Pontefract, Yorkshire. [2769]

ARCHITECTURAL Assistants required small office, intermediate and post intermediate standard. Write giving details salary and experience.—M. Rainford Fletcher & Partners, 13 Ambrose Place, Worthing, Sussex. [2778]

J. DOUGLASS MATHEWS & PARTNERS, Chartered Architects, 3 Ebury Street, London, E.W.1, require further medium grade Assistants. Salaries in accordance with experience. It would be helpful if previously unsuccessful applicants do not apply. [2752]

LONDON firm of Architects require Final Standard Assistant. CENTRAL 7748. [2777]

POST-INTERMEDIATE Assistant required, in large London office with widely varied practice.—Lewis Solomon, Son & Joseph, 21 Bloomsbury Way, London, W.C.1. Telephone. HOL. 7082. [0010]

TROFDEK—Senior and Junior assistants required immediately for design department and drawing office in Lincoln. Applicants with general structural background and building construction experience will be given responsible position, high salary, very congenial working conditions and excellent prospects for rapid advancement. Please write fully.—Box 4801. [2781]

ARCHITECTURAL APPOINTMENTS VACANT—contd.

QUALIFIED Architect's Assistant age 23 to 30 required in progressive London office. Salary £450—£450 according to age and experience.—Box No. 4692, c/o A. & B.N. [2774]

ARCHITECTURAL APPOINTMENTS WANTED

A.R.I.B.A. wide experience.. seeks responsible position; minimum salary £1,000 p.a.—Box 4669. [2774]

GRANADA TV require staff architect for general duties and also to help with development of their TV Centre. Write giving age, experience, salary required to Sidney L. Bernstein, Granada TV Network, Limited, Water Street, Manchester. 3. [2775]

SITUATIONS VACANT

SENIOR (TECHNICAL) SALES REPRESENTATIVE CONCRETE PLANT

OPENING occurs in new Division of National Company for man with first class sales record, able to handle top level and site interviews. Must possess knowledge of concrete with experience in selling and demonstrating vibrators, mixers, etc. Position offers scope and promotional prospects to right applicant. Apply giving full details of experience to Box No. 4543, c/o A. & B. N. [2761]

SERVICES OFFERED

A.R.I.B.A. offers part time assistance in any capacity.—Box 4670. [2770]

FOR SALE

JOINTLESS composition flooring in attractive colour range—quotations free—Full particulars from the Liotex Asbestos Flooring Co. Ltd., 3, Corbette Passage, London, S.E.16. (Dept. A). BERNOLSEY 4341-2-3. [0622]

FOR SALE—contd.

ALL hardwood mouldings, plain and embossed, embossed ornaments and dowels. Send for catalogue and today's lowest trade prices.—Dareve's Moulding Mills, Ltd., 30, Pownall Road, Dalston, E.8. Clissold 1543/4. [0144]

CAN-TILE Liquid floor coating for canteens, hospitals, shops, factories, toilets. Cost 20% of lino. Write Dohm Ltd., 167 Victoria St., London, S.W.1. Dohm's Can-Tile. [2660]

FOAMED plastic eye and ridge filler, non-inflammable, contoured to corrugated and other shapes.—Laundry Supply Co., Plastic Division, 209 Clarkson Road, Glasgow, S.4. [2716]

RECONDITIONED ex-Army Huts and Manufactured Buildings. Timber, Asbestos, Nissen type, Hall type, etc. All sizes and prices.—Write call or telephone, Universal Supplies (Belvedere) Ltd., Crabtree Manorway, Belvedere, Kent, Erith 2948. [0062]

ABOUT 3,000 old hand-made 2 inch bricks for sale.—Wilts. Excellent condition.—Box No. 4826. [2755]


MISCELLANEOUS

MURAL Paintings for Restaurants, Classrooms, Entrance Halls, etc. Classic or Modern styles. Tate Studios, 221 Acton Lane, Chiswick, London, W.4. Tel. CHISWICK 5841. [2772]

BOOKS

MATERIAL Handling in Works Stores: The Fork-Lift Truck and Pallet System. Second edition. By L. J. Hoefkens. Shows how the use of fork-lift trucks and pallets in industrial stores can increase production, utilize floor space more effectively, help control of movement and reduce costs. Includes a description of a system actually operated in a modern factory. 18s net, from all booksellers. By post 18s 11d from The Publishing Department, Dorset House, Stamford Street, London, S.E.1.

PLASTICS Progress: Papers and Discussions at the British Plastics Convention, 1956. The complete text, illustrated, of the papers together with a full report of the discussion. Subjects include: Polymer structure and properties; Expanded plastics; Thermoplastics; Extrusion; Work study and productivity; Injection moulding; Foams; Foundry resins; and Glass reinforced plastics. 80s net, from all booksellers. By post 81s 8d from Publishing Department, Dorset House, Stamford Street, London, S.E.1.



'It is with every confidence that this book can be recommended'

Local Government Chronicle

A practical book on all aspects building design and construction

By Edwin Gunn, A.R.I.B.A. Revised by John Brandon-Jones A.A.D.P., A.R.I.B.A.

Fully revised edition of a well-known reference book on constructional design. Containing a lifetime's first-hand experience, proved on the building site, it is an indispensable tool for both the architect and the builder. A valuable feature is the large number of references to publications of such bodies as the Building Research Station and the British Standards Institution.

9½ in. by 6 in. 188 pp. 183 Illustrations.

Essential to all architects, students and building craftsmen. 3rd. Ed. 21s. net By post 21s. 10d.

from all booksellers

Published for "The Architect & Building News" by

ILLIFFE AND SONS LIMITED • DORSET HOUSE • STAMFORD STREET • LONDON • S.E.1

INDEX TO ADVERTISERS

Official Notices, Tenders, Auctions, Local and Miscellaneous Appointments on pages 48 and 49

| | | | | | | | |
|---|----|--|-----|--|----|---|-----|
| Abix (Metal Industries) Ltd. | — | Crittall Manfg. Co. Ltd., The | — | Johnson's Reinforced Concrete Engineering Company Ltd. | — | Runnymede Rubber Co. Ltd. | — |
| Acrow (Engineers) Ltd. | 45 | Culium, H. W., & Co. Ltd. | 40 | Kay & Co. (Engineers) Ltd. | 37 | Ryjack Productions Ltd. | — |
| Aerialite Ltd. | — | Curfew Doors & Shutters Ltd. | — | Kay, Fredk. (Engineering) Ltd. | — | Sadd, John, & Sons Ltd. | — |
| Adam & Lane & Neeve Ltd. | — | Curwen & Newbery Ltd. | — | Kerner-Greenwood & Co. Ltd. | — | Salopian Engineers Ltd. | — |
| Adams Hydraulics Ltd. | — | Cutting, R. C. | — | King, Geo. W. Ltd. | — | Sanders, Wm., & Co. (Wednesbury) Ltd. | — |
| Adams, Robert (Victor) Ltd. | — | Dale, John, Ltd. | — | King, J. A., & Co. Ltd. | — | Sankey, J. H., & Son Ltd. | — |
| Adametz Ltd. | — | Dalton, Ballard & Co. Ltd. | — | Kings Langley Eng. Co. Ltd. | — | Seaboard Lumber Sales Co. Ltd. | — |
| Aldam, E. Hill, & Co. Ltd. | 24 | Danaura Ltd. | — | Klinger, Richard, Ltd. | — | Sealanco (St. Helens) Ltd. | — |
| Allied Brick and Tile Works Ltd. | — | De la Rue, Thos., & Co. Ltd. | 2 | Lacrinoid Products Ltd. | — | Secomastic Ltd. | 36 |
| Alfol Insulation Ltd. | 40 | Dennison, Kett & Co. Ltd. | 36 | Laing, John, & Son Ltd. | — | Semtex Ltd. | — |
| Ames Crosta Mills & Co. Ltd. | — | Dent Edwards Paints Ltd. | 28 | Lambhill Ironworks Ltd. | — | Schavarian Sheet Metal & Engineering Co. Ltd. | IBC |
| Ancoirite Ltd. | 14 | Denny Mott & Dickson Ltd. | 44 | Lane & Girvan Ltd. | — | Shell Chemical Co. Ltd. | — |
| Arabol Manufacturing Co. Ltd. | — | Destrol Sales Ltd. | — | Latter, A., & Co. Ltd. | — | Shutter Contractors Ltd. | 44 |
| The | — | Dexion Ltd. | 42 | Lead Sheet & Pipe Council | 16 | Signeriffs Ltd. | 46 |
| Armstrong Cork Co. Ltd. | — | Dohm Ltd. | — | Le Bas Tube Co. Ltd. | — | Simsen, Thos., & Co. Ltd. | — |
| Associated Metal Works (Glasgow) Ltd. | — | Dowson & Mason Ltd. | — | Lewis, G. W., Tileries Ltd. | — | Sissons Bros. & Co. Ltd. | — |
| Atlas Preservative Co. Ltd. | — | Dunlop Rubber Co. Ltd. | — | Light Steelwork (1925) Ltd. | — | Small & Parkes Ltd. | — |
| Atlas Stone Co. Ltd. | — | Dunlop and Ranken Ltd. | — | Lindsay's Paddington Iron Works (1948) Ltd. | — | Smith, Samuel, & Sons Ltd. | — |
| Austin, James, & Sons (Dewsbury) Ltd. | — | Durastel Ltd. | — | Lion Foundry Co. Ltd. | — | Smith, Thomas, & Son Ltd. | 27 |
| Avery, J., & Co. Ltd. | — | Duresco Products Ltd. | — | Liquilite Supply Co. | 46 | Smith's Fireproof Floors Ltd. | — |
| Baldwin, Son & Co. Ltd. | — | Dussek Bros., & Co. Ltd. | — | Logical Fuel Storage Units | 4 | Solignum Ltd. | — |
| Bambergers Ltd. | — | Dussek Bitumen & Taroleum Ltd. | — | London Brick Co. Ltd. | — | Sommerfelds Ltd. | — |
| Barking Brassware Co. Ltd. | — | Economic House Drainage Rpg. Co. Ltd., The | — | Lumenated Ceilings Ltd. | — | Soundproof Construction Ltd. | — |
| Barry, Ostlers & Shepherd Ltd. | 12 | Edison Swan Electric Co. Ltd., The | — | Luxfer Ltd. | — | Staedler, J. S., Ltd. | — |
| Bath & Portland Stone Firms Ltd. | — | Ellard Sliding Door Gears Ltd. | 17 | MacAndrews & Forbes Ltd. | — | Stainless Steel Sink Co. Ltd., The | 35 |
| Batley, Ernest, Ltd. | 46 | Electrolux Ltd. | — | Magnesium Ltd. | — | Standard Metal Window Co., The | — |
| Baume & Co. Ltd. | — | Ellis, John, & Sons Ltd. | — | Manger, J., & Son Ltd. | 39 | Standard Patent Glazing Co. Ltd. | — |
| Bawn, W. B., & Co. Ltd. | 43 | Empire Stone Co. Ltd. | 35 | Margolis, M. | 35 | Stanley, W. F., & Co. Ltd. | — |
| Bawns Pressings Ltd. | — | Engert & Rolfe Ltd. | — | Margolis, S., & Sons | 29 | Steel Bracketing & Lathing Ltd. | — |
| Baxendale & Co. Ltd. | 42 | English Joinery Manfg. Assocn., The | — | Marley Tile Co. Ltd., The | — | Steel Radiators Ltd. | — |
| Bell & Webster & Co. Ltd. | — | En-Tout-Cas Co. Ltd., The | — | Marriott, Robt., Ltd. | — | Stelcon (Industrial Floors) Ltd. | 5 |
| Berger, Lewis (Great Britain) Ltd. | — | Esavian Ltd. | — | Marrat & Scott Ltd. | 47 | Steven, A. & P., Ltd. | — |
| Berry Wiggins & Co. Ltd. | — | Eso Petroleum Co. Ltd. | 33 | Mather & Platt Ltd. | — | Stevenson, J., & Sons Ltd. | — |
| Beynon, T., & Co. Ltd. | — | Expanded Metal Co. Ltd., The | — | McCarthy, M., & Sons Ltd. | 35 | Stie B Paints Ltd. | 47 |
| Black Sheathing Felt Campaign | — | Expandite Ltd. | — | Mealing Bros. Ltd. | 35 | Stillite Products Ltd. | — |
| Blackwells & National Roofings Ltd. | 41 | Faculty of Architects and Surveyors, The | — | Medway Buildings & Supplies Ltd. | — | Storrie Smithson & Co. Ltd. | — |
| Blackwell, Wyckham, & Co. Ltd. | — | Farmer, S. W., & Son Ltd. | — | Merediths Ltd. | — | Stramit Boards Ltd. | — |
| Blackley Cabinet & Metal Works Ltd. | — | Fibre-glass Ltd. | — | Minton Hollins Ltd. | — | Stuart's Granolithic Co. Ltd. | — |
| Blundell, Spence & Co. Ltd. | 34 | Finch, B., & Co. Ltd. | — | Moler Products Ltd. | — | Sugg, Wm., & Co. Ltd. | — |
| Boddy Roofing Co. Ltd. | — | Finlock Gutters Ltd. | — | Morris Singer Co. | — | Sun Insurance Office Ltd. | — |
| Bolton Gate Co. Ltd. | — | Flavel, Sidney, & Co. Ltd. | 18 | Mullen & Lumsden Ltd. | — | Sundaels Board Co. Ltd. | — |
| Booth, H., & Sons Ltd. | — | Flexaire Ltd. | — | Murex Welding Processes Ltd. | — | Surflex Flooring Co. Ltd. | 38 |
| Bostwick Gate & Shutter Co. Ltd. | 35 | Flush Woodwork Ltd. | — | Myton Ltd. | — | Surrey Concrete Ltd. | — |
| Bowater Sales Co. Ltd. | — | Franki Compressed Pile Co. Ltd., The | — | National Association of Master Asphalters | — | Sussex Cement & Concrete Products | — |
| Braby, F., & Co. Ltd. | — | Freeman, Joseph, Sons & Co. Ltd. | — | National Coal Board, The | — | Synchronome Co. Ltd., The | 35 |
| Bradford, F., & Co. Ltd. | — | French, Thos., & Sons Ltd. | — | New Day Electrical Accessories Ltd. | 38 | Szerelmey Ltd. | — |
| Brady, G., & Co. Ltd. | — | Gardner, J., & Co. Ltd. | — | Newman, John, Ltd. | — | Tabula Chalkboards Ltd. | — |
| Braim-Arc Ltd. | — | Gas Council, The | — | Newman, Wm., & Sons Ltd. | — | Tarmac Ltd. | — |
| Bratt Colbran Ltd. | — | Gaskell & Chambers Ltd. | — | Newsam, H., Sons & Co. Ltd. | — | Teleflex Products Ltd. | — |
| Briggs, Wm., & Sons Ltd. | 11 | General Electric Co. Ltd., The | 22 | Noelite Ltd. | — | Temperature Ltd. | — |
| British Aluminium Co. Ltd. | — | The Gimson & Co. (Leicester) Ltd. | — | Norm Ltd. | — | Templex Holdings Ltd. | — |
| British Bitumen Emulsions Ltd. | — | Glazed & Floor Tile Manufacturers' Association | 1 | Norharc Organisation, The | — | Tentest Fibre Board Co. Ltd. | — |
| British Columbia Lumber Mfrs. Association | — | Gliksten, J., & Son Ltd. | — | Norwood Steel Equipment Ltd. | 32 | Thames Plywood Manufacturers Ltd. | — |
| British Constructional Steelwork Association | — | Grange-Camelon Iron Co. Ltd. | — | Nu-Swift Ltd. | — | Thermacoast Ltd. | — |
| British Ebonite Co. Ltd., The | — | Gray, J. W., & Son Ltd. | 37 | Odoni, A. A., & Co. Ltd. | — | Thermocontrol Installations Co. Ltd. | — |
| British Electrical Development Association | — | Greenwood's & Airvac Ventilating Co. Ltd. | — | Ordnance Survey, The | — | Thom, J., Ltd. | 44 |
| British Hermes Ltd., The | — | Grundy, J., Ltd. | — | Ornamental Gate Co., The | — | Thompson, John, Beacon Windows Ltd. | — |
| British Mouldex Ltd. | — | Gulf Radiators Ltd. | — | Paramount Asphalt Ltd. | — | Thorn Electrical Industries Ltd. | — |
| British Paints Ltd. | — | Gummers Ltd. | — | Parmiter, Hope & Sugden Ltd. | — | Thorn, J., & Sons Ltd. | 24 |
| British Plaster Board (Manufacturing) Ltd., The | 23 | Hale & Hale Ltd. | — | Parker, Winder & Achurch Ltd. | — | Thornton, William, & Sons Ltd. | — |
| British Plumber Ltd. | — | Hall Harding Ltd. | — | Parsons, Thos., & Sons Ltd. | — | Thorp, J. B. | — |
| British Reinforced Engineering Co. Ltd., The | — | Hall, J. & E., Ltd. | — | Partridge, Wilson & Co. Ltd. | — | Tile-Art Flooring Co. Ltd. | — |
| British Replin Ltd. | — | Hall & Kay Ltd. | — | Penfold Fencing & Eng. Ltd. | 45 | Timber Development Association Ltd., The | — |
| British Titan Products Co. Ltd. | — | Hammer, Geo. M., & Co. Ltd. | — | Permaflex Ltd. | — | Tretex Ltd. | — |
| British Trolley Track Co. Ltd., The | — | Hammond & Champness Ltd. | — | Permanite Ltd. | — | Tretol Ltd. | — |
| Brockhouse, J., & Co. Ltd. | — | Hangers Paints Ltd. | — | Petrade Ltd. | — | Trianco Ltd. | 40 |
| Bryce White & Co. Ltd. | — | Harvey, G. A., & Co. (London) Ltd. | — | Philips Electrical Ltd. | — | Troughton & Young (Lighting) Ltd. | — |
| Burn Bros. (London) Ltd. | — | Haskins | 7 | Phoenix Rubber Co. Ltd. | — | Tucker & Edgar | 44 |
| Cafferata & Co. Ltd. | — | Hathenware Ltd. | — | Pickerings Ltd. | — | Turner, Charles & Son Ltd. | — |
| Callow Rock Lime Co. Ltd., The | — | Henderson, P. C. Ltd. | — | Pierhead Ltd. | — | Turners Asbestos Cement Co. Ltd. | 25 |
| Canada, Government of. | 10 | Henley's P. T. Telegraph Works, Co. Ltd. | OBC | Pilkington Bros. Ltd. | 9 | Twistall Reinforcement Ltd. | — |
| Canna Ltd. | — | Hewitt, F. & D. M., Ltd. | — | Pilkington's Tiles Ltd. | — | Tyrol Sales Ltd. | — |
| C. & P. Development Co. (London) Ltd. | — | Hilger & Watts Ltd. | — | Playlax Ltd. | 21 | Union Fibre Pipes (Great Britain) Ltd. | 31 |
| Cape Asbestos Co. Ltd., The | — | Hill, Richard, Ltd. | — | Pollard, E., & Co. Ltd. | — | Unique Balance Co. Ltd. | — |
| Carborundum Co. Ltd., The | 35 | Hills, F., & Sons Ltd. | — | Potter, F. W., & Soar Ltd. | — | United Merchants Ltd. | — |
| Celotex Ltd. | — | Hills (West Bromwich) Ltd. | 19 | Prodit Ltd. | — | United Steel Companies Ltd., The | — |
| Cement Marketing Co. Ltd., The | — | Holland & Hannen and Cubitts Ltd. | 13 | Pyronex Ltd. | 20 | Veitchi Company Ltd., The | — |
| Central Electricity Authority | 42 | Holophone Ltd. | — | Radiation Ltd. | 6 | Velux Co. Ltd. | — |
| Chase Products (Engineering) Ltd. | — | Holoplast Ltd. | — | Raines & Porter Ltd. | 3 | Versatile Fittings (W.H.S.) Ltd. | — |
| Chatwood-Milner Ltd. | — | Home Fittings (Gt. Britain) Ltd. | — | Rainham Timber Engineering Co. Ltd. | — | Vigers Bros. Ltd. | — |
| Cheecol Processes Ltd. | — | Hope, Henry & Sons Ltd. | — | Rapid Floor Co. Ltd., The | 26 | Vulcanite Ltd. | — |
| Cheetham, A. J., Ltd. | — | Hotchkiss Engineers Ltd. | — | Ratcliffe Bros. Ltd. | — | Ward, Thos. W., Ltd. | — |
| Chesterman, J., & Co. Ltd. | — | Hunter, Douglas (Great Britain) Ltd. | — | Redpath Brown & Co. Ltd. | 46 | Water Softener & Vacuum Cleaner Service Ltd. | — |
| Chilton Steel Ltd. | — | Ibstock Brick & Tile Co. Ltd. | — | Reliable Plywood Co. Ltd. | — | West's Piling & Construction Co. Ltd. | — |
| Churchouse, C. M., Ltd. | — | Ilife & Sons Ltd. | — | Reynolds, H. L., Ltd. | — | Wednesbury Tube Co. Ltd., The | — |
| Cloughton Bros. Ltd. | — | Imperial Chemical Industries Ltd. | — | R.I.W. Protective Products Co. Ltd. | — | Williams, John, & Sons (Cardiff) Ltd. | — |
| Clement Bros., Haslemere, Ltd. | — | Ironite Co. Ltd., The | — | Richardson & Starling Ltd. | 26 | Wood, Edward, & Co. Ltd. | 8 |
| Code Designs Ltd. | — | Isola-Lisbon | — | Ripper Building Works Ltd. | 37 | Yale & Towne Manufacturing Co. | 30 |
| Colthurst Symons & Co. Ltd. | — | Jablo Plastic Industries Ltd. | — | Rolyat Tank Co. Ltd., The | 22 | Yorkshire Copper Works Ltd. | — |
| Conder Engineering Co. Ltd. | 41 | Janes, H. C., Ltd. | — | Rubber Improvement Ltd. | 43 | Youngman, W. C., Ltd. | 39 |
| Compactom Ltd. | — | Jones, T. C., & Co. Ltd. | — | Ruberoid Co. Ltd., The | — | | |
| Conex-Terna Ltd. | — | Jones & Broadbent Ltd. | — | | | | |
| Costain, Richard, Ltd. | — | Johnson Bros. Ltd. | — | | | | |
| Cox & Co. (Watford) Ltd. | — | | | | | | |
| Cox, William J., Ltd. | — | | | | | | |
| Cozens Ventilators Ltd. | 36 | | | | | | |

If no page number is quoted, please see previous issues.

dribble . . .
. . . dribble
dribble . . .
. . . down
the wall




The best way to keep rainwater in it's proper place is to specify Smeco 14 swg rainwater goods. No bursting. No rusting. No breakages, **CHEAPER THAN CAST IRON TOO!**

Descriptive literature available.

SMECO

PRESSED STEEL RAINWATER GOODS


Schaverien Sheet Metal & Engineering Co. Ltd., Moarain House,
Cambridge Heath Road, London, E.2 Tel : Bishopsgate 0330



A view of the Velindre Works showing extension to the Cold Reduction Plant under construction.

HENLEY'S are proud to be associated with the important project of the cold reduction plant which recently went into production at the Velindre Works of the Steel Company of Wales. It is here, forming an integral part of the new project, that HENLEY'S Contract Department are installing fifty miles of lead-sheathed and aluminium-sheathed HENLEY Paper and P.V.C. Insulated Cables.

Cable installation in progress.



The 5-stand Mill at the Velindre Works which has now gone into operation.

LET

HENLEY

CABLES CARRY THE CURRENT

